

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0010 URBAN	0010 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0003 URBAN	0003 URBAN
28000510	INLET FILTERS	EACH	178	143														35
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	55804	45090														10714
28200200	FILTER FABRIC	SQ YD	534															534
28300400	AGGREGATE DITCH	TON	288															288
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	6270	6010														260
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	31893	31893														
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	36343	16005										1025	3582		441	15290
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	3792															3792
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	28188	28188														
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	629	629														
40600300	AGGREGATE (PRIME COAT)	TON	13	13														
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	182	182														

X SPECIALTY ITEM

- A ROADWAY AND DRAINAGE - 100% STATE
- B RETAINING WALL SN 022-W063 - 100% STATE
- C RETAINING WALL SN 022-W064 - 100% STATE
- D RETAINING WALL SN 022-W065 - 100% STATE
- E RETAINING WALL SN 022-W066 - 100% STATE
- F BRIDGE SN 022-2029 - 100% STATE
- G BRIDGE SN 022-2030 - 100% STATE

- H LIGHTING - 100% STATE
- I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT 100% STATE
- J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE
- K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE
- L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE

- M SHARED-USE PATH - 100% NAPERVILLE
- N ROADWAY ITEMS - 100% STATE
- O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY

FILE NAME	USER NAME - EUSER	DESIGNED <i>FJO</i>	REVISED	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE#		DRAWN <i>KES</i>	REVISED		338	(112 & 113) WRS-5	DUPAGE	963	8				
FEET SCALE - 1"=SCALE		CHECKED <i>JCM</i>	REVISED		SCALE: SHEET NO. 3 OF 41 SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT				
FEET DATE - MONTH		DATE <i>10/15/2012</i>	REVISED		CONTRACT NO. 60131								