

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0010 URBAN	0010 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0003 URBAN	0003 URBAN
60500060	REMOVING INLETS	EACH	32	31													1	
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	1														1	
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	2	2														
60602800	CONCRETE GUTTER, TYPE B	FOOT	1132	1132														
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	384	384														
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	7756	7344													412	
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	2819	2819														
60607900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	476	476														
60609100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (VARIABLE WIDTH GUTTER FLAG)	FOOT	169	169														
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	261	261														
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1175	1175														
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	6109	6109														

X SPECIALTY ITEM

- | | | |
|---|--|---|
| A ROADWAY AND DRAINAGE - 100% STATE | H LIGHTING - 100% STATE | M SHARED-USE PATH - 100% NAPERVILLE |
| B RETAINING WALL SN 022-W063 - 100% STATE | I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE | N ROADWAY ITEMS - 100% STATE |
| C RETAINING WALL SN 022-W064 - 100% STATE | J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE | O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY |
| D RETAINING WALL SN 022-W065 - 100% STATE | K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE | |
| E RETAINING WALL SN 022-W066 - 100% STATE | L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE | |
| F BRIDGE SN 022-2029 - 100% STATE | | |
| G BRIDGE SN 022-2030 - 100% STATE | | |

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILE NO.		DRAWN	REVISED			338	(112 & 113) WRS-5	DUPAGE	963	18	
FILE SCALE		CHECKED	REVISED			SCALE: SHEET NO. 13 OF 41 SHEETS STA. TO STA.		CONTRACT NO. 60131			
FILE DATE		DATE	REVISED			ILLINOIS FED. AID PROJECT					