

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003	0040	0040	0040	0040	0010	0010	0021	0021	0021	0021	0028	0028	0003	0003
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
X 81800400	AERIAL CABLE, 4-1/2 NO. 2 WITH MESSENGER WIRE	FOOT	10774															10774
X 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	13								13							
X 82105700	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT	EACH	24								24							
X 83050800	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 12 FT. MAST ARM	EACH	13								13							
X 83501400	LIGHT TOWER, 90 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 6	EACH	4								4							
X 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	108								108							
X 83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	64								64							
X 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	13								13							
X 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1									1						
X 86400100	TRANSCEIVER - FIBER OPTIC	EACH	2									2						
X 87101100	FIBER OPTIC CABLE ON MESSENGER, NO. 62.5/125, 4F	FOOT	1181								1181							
X 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4682								270	4412						

X SPECIALTY ITEM

- A ROADWAY AND DRAINAGE - 100% STATE
- B RETAINING WALL SN 022-W063 - 100% STATE
- C RETAINING WALL SN 022-W064 - 100% STATE
- D RETAINING WALL SN 022-W065 - 100% STATE
- E RETAINING WALL SN 022-W066 - 100% STATE
- F BRIDGE SN 022-2029 - 100% STATE
- G BRIDGE SN 022-2030 - 100% STATE

- H LIGHTING - 100% STATE
- I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE
- J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE
- K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE
- L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE

- M SHARED-USE PATH - 100% NAPERVILLE
- N ROADWAY ITEMS - 100% STATE
- O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY

FILE NAME	USER NAME - USER#	DESIGNED <i>PA</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILES		DRAWN <i>AES</i>	REVISED -		338	(112 & 113) WRS-5	DJ/PAGE	963	27				
		CHECKED <i>JCM</i>	REVISED -		SCALE: SHEET NO. 22 OF 41 SHEETS STA. TO STA.				CONTRACT NO. 60131				
		DATE <i>10/15/2012</i>	REVISED -		ILLINOIS FED. AID PROJECT								