

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0010 URBAN	0010 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0003 URBAN	0003 URBAN
X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	2821	2821														
X6350110	DELINEATORS (SPECIAL)	EACH	85															85
X6350120	DELINEATOR REMOVAL	EACH	73															73
X6370050	CONCRETE BARRIER WALL (SPECIAL)	FOOT	256	256														
X6380205	TEMPORARY MODULAR GLARE SCREEN	FOOT	8100															8100
X6640535	CHAIN LINK FENCE, 6' ATTACHED TO STRUCTURE	FOOT	88	88														
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	7	7														
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1														
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	87	87														
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	50 FT	5032	2075														2957
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	317950	57187														260763
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	16845	10594														6251

X SPECIALTY ITEM

A ROADWAY AND DRAINAGE - 100% STATE  
 B RETAINING WALL SN 022-W063 - 100% STATE  
 C RETAINING WALL SN 022-W064 - 100% STATE  
 D RETAINING WALL SN 022-W065 - 100% STATE  
 E RETAINING WALL SN 022-W066 - 100% STATE  
 F BRIDGE SN 022-2029 - 100% STATE  
 G BRIDGE SN 022-2030 - 100% STATE

H LIGHTING - 100% STATE  
 I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE  
 J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE  
 K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE  
 L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE

M SHARED-USE PATH - 100% NAPERVILLE  
 N ROADWAY ITEMS - 100% STATE  
 O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILED		DRAWN	REVISED									338	(112 & 113) WRS-5	DUPAGE	963	37
	PLANT SCALE	CHECKED	REVISED					SCALE: SHEET NO. 32 OF 41 SHEETS STA. TO STA.				CONTRACT NO. 60131				
	PLOT DATE	DATE	REVISED									ILLINOIS FED. AID PROJECT				