

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003	0040	0040	0040	0040	0010	0010	0021	0021	0021	0021	0028	0028	0003	0003
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
X JS816072	UNIT DUCT, WITH 2-1/C NO. 2 AND 1/C NO. 4 GROUND, 600V (XLP-TYPE USE), 2" DIA. CNC	FOOT	898															898
X JS816076	UNIT DUCT, WITH 4-1/C NO. 2 AND 1/C NO. 4 GROUND, 600V (XLP-TYPE USE), 2" DIA. CNC	FOOT	9517															9517
X JS817211	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	532															532
X JS817214	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	152															152
X JS817215	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	608															608
X JS817218	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	99															99
X JS821001	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	3															3
X JS821002	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8															8
X JS821009	TEMPORARY LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750WATT	EACH	28															28
X JS825004	LIGHTING CONTROLLER, 200 AMPERE	EACH	1															1
X JS828002	LIGHTING CONTROLLER FOUNDATION, TYPE B	EACH	1															1
X JS830025	TEMPORARY WOOD POLE, 40 FT., CLASS 4	EACH	2															2

X SPECIALTY ITEM

- A ROADWAY AND DRAINAGE - 100% STATE
- B RETAINING WALL SN 022-W063 - 100% STATE
- C RETAINING WALL SN 022-W064 - 100% STATE
- D RETAINING WALL SN 022-W065 - 100% STATE
- E RETAINING WALL SN 022-W066 - 100% STATE
- F BRIDGE SN 022-2029 - 100% STATE
- G BRIDGE SN 022-2030 - 100% STATE

- H LIGHTING - 100% STATE
- I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE
- J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE
- K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE
- L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE

- M SHARED-USE PATH - 100% NAPERVILLE
- N ROADWAY ITEMS - 100% STATE
- O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY

FILE NAME	USER NAME - USER1	DESIGNED PJO	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET	
FILE #	DRAWN KES	REVISED -	33B			(112 & 113) WRS-5	DUPAGE	963	43	
PLST SCALE - 1/4"=1'-0"	CHECKED JCM	REVISED -	SCALE:			SHEET NO. 38 OF 41 SHEETS		STA.	TO STA.	
PLST DATE - 10/15/2012	DATE 10/15/2012	REVISED -						ILLINOIS FED. AID PROJECT		
						CONTRACT NO. 60131				