



PROPOSED TYPICAL SECTION
INTERSTATE-88
STA 6526+56 TO STA 6528+72

ILLINOIS TOLLWAY LEGEND PROPOSED

- ☐ 1 PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)
- ☐ 2 PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED)
- ☐ 3 CONTINUOUSLY REINFORCED P.C.C. PAVEMENT 12"
- ☐ 4 SUBGRADE AGGREGATE, 12"
- ☐ 5 SUBGRADE AGGREGATE SPECIAL, 6"
- ☐ 6 DRILLED AND GROUTED IN PLACE, TIE BARS 3/4" X 24" AT 24" CTS. (INCLUDED IN COST OF PAVEMENT)
- ☐ 7 GUTTER, TYPE G-2
- ☐ 8 GUTTER, TYPE G-2 MODIFIED
- ☐ 9 HOT-MIX ASPHALT SHOULDERS, 6"
- ☐ 10 STABILIZED SUBBASE HOT-MIX ASPHALT, 4"

- ☐ 11 AGGREGATE SHOULDERS, TYPE B
- ☐ 12 AGGREGATE SHOULDERS SPECIAL, TYPE C
- ☐ 13 GALVANIZED STEEL PLATE BEAM GUARDRAIL, 6' POSTS
- ☐ 14 SOLDIER PILE RETAINING WALL WITH 42" CONCRETE BARRIER
- ☐ 15 TOPSOIL EXCAVATION AND PLACEMENT, 8"
- ☐ 16 SEEDING
- ☐ 17 PIPE UNDERDRAINS, FABRIC LINED TRENCH 6"
- ☐ 18 SLOPE WALL (SEE BRIDGE DRAWINGS)
- ☐ 19 PORTLAND CEMENT CONCRETE SHOULDER 6"
- ☐ 20 RIGHT OF WAY FENCE, 6'

NOTES

1. SEE CROSS SECTIONS FOR GRADING INFORMATION.
2. SEE LANDSCAPING PLANS FOR SEEDING AND SODDING INFORMATION.
3. SEE PLANS FOR PLACEMENT OF GUARDRAIL
4. SEE UNDERDRAIN PLANS FOR PLACEMENT OF UNDERDRAINS

FILE NAME =	USER NAME = #USER#	DESIGNED <i>PJO</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS ILLINOIS ROUTE 59	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN <i>KES</i>	REVISED -			338	(112 & 113) WRS-5	DUPAGE	963	57	
PLOT SCALE = #SCALE#		CHECKED <i>JCM</i>	REVISED -			CONTRACT NO. 60I31					
PLOT DATE = #DATE#		DATE <i>10/15/2012</i>	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. 11 OF 17 SHEETS		STA.	TO STA.		