℄ IL ROUTE 59 RAMP D
PROPOSED R.O.W.
CONCRETE GUTTER, TYPE B AT SN 022-W063 (SEE NOTE 4)
PROPOSED RETAINING WALL SN 022-W063 (SEE NOTE 4)
EXISTING R.O.W.
MATCH LINE STA. 913+00 (NB)
FOR CONTINUATION SEE RAMP D PLAN/PROFILE SHEETS
COMB CC&G TB9.24 STA. 914+05 TO STA. 915+27 (SEE NOTE 2)
10" AGGREGATE SHOULDERS TYPE B
PROPOSED 5' SIDEWALK (TYP.)
GALV. SPBGR TY A 6FT POSTS
COMB CC&G TB6.24
CONC MED TSB9.24 (SEE ROADWAY DETAIL)
SEE NOTE 5
IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2
TRAFFIC BARRIER TERMINAL, TYPE T6
℄ PROPOSED IL ROUTE 59 NB (SEE NOTE 1)
BRIDGE APPR PAVT (SEE NOTE 4)
ILLINOIS - ROUTE 59 (NB)
R=8'
R=6'
CH LK FENCE 6 AT STR (SEE NOTE 3)
CONC MEDIAN SURF 4
SEE CONCRETE BARRIER DETAIL
BR APPR PVT CON (PCC) (SEE STD. 420401)
SEE NOTES 2 & 3
LANDSCAPE MEDIAN
COMB CC&G TB9.24 (SEE NOTE 2)
PROPOSED R.O.W.
PORTLAND CEMENT CONCRETE PAVEMENT, 10 1/4" (JOINTED)
10" AGGREGATE SHOULDERS TYPE B
PROPOSED SHARED-USE PATH, 10' (SEE NOTE 3)
℄ IL ROUTE 59 RAMP A
PROPOSED IL ROUTE 59 ℄
INTERSTATE 88
LANDSCAPE MEDIAN
COMB CC&G TB6.24 (SEE NOTE 2)
CH LK FENCE 5'
PROPOSED RETAINING WALL SN 022-W064 (SEE NOTE 4)
CONCRETE GUTTER, TYPE B AT SN 022-W064 (SEE NOTE 4)
RIGHT-OF-WAY FENCE TYPE 1, 6'
GUTTER, TYPE G-2
SEE NOTE 2 & 5
COMB CC&G TB6.24 STA. 913+00 TO STA. 914+05
FOR CONTINUATION SEE RAMP A PLAN/PROFILE SHEETS
INFORMATION SHOWN IS FOR NORTHBOUND PROFILE
SEE SOUTHBOUND PROFILE SHEETS FOR MORE INFORMATION
- SEE PRIOR SHEET FOR PLAN NOTES
GALV. SPBGR TY A 6FT POSTS
PROPOSED 5' SIDEWALK (SEE NOTE 3)
10" AGGREGATE SHOULDERS TYPE B
COMB CC&G TB6.24
COMB CC&G TB9.24 (SEE NOTE 2)
PROP. R.O.W.
TRAFFIC BARRIER TERMINAL, TYPE T5
BR APPR PVT CON (PCC) (SEE STD. 420401)
BRIDGE APPR PAVT (SEE NOTE 4)
SEE CONCRETE BARRIER DETAIL
EXISTING R.O.W.
PROPOSED R.O.W.
LANDSCAPE MEDIAN
10" AGGREGATE SHOULDERS TYPE B
PROPOSED 10' SHARED-USE PATH (SEE NOTE 3)
SEE NOTES 2 & 5
FOR CONTINUATION SEE RAMP B PLAN/PROFILE SHEETS
FOR CONTINUATION SEE RAMP C PLAN/PROFILE SHEETS
℄ IL ROUTE 59 RAMP C
SEE NOTES 2 & 5
CONCRETE GUTTER, TYPE B AT SN 022-W065 (SEE NOTE 4)
PROPOSED RETAINING WALL SN 022-W065 (SEE NOTE 4)
SEE NOTE 5
COMB CC&G TB9.24 (SEE NOTE 2)
MATCH LINE STA. 927+00 (NB)
LANDSCAPE MEDIAN
CH LK FENCE 5'
COMB CC&G TB6.24
CONCRETE GUTTER, TYPE B AT SN 022-W066 (SEE NOTE 4)
PROPOSED RETAINING WALL SN 022-W066 (SEE NOTE 4)
TRAFFIC BARRIER TERMINAL, TYPE T2
GUTTER, TYPE G-2
GALV. SPBGR TY A 6FT POSTS
℄ IL ROUTE 59 RAMP B

HORIZONTAL SCALE: 1"=50'-0"
VERTICAL SCALE: 1"=5'-0"

VPI STA. 920+56.57
EL. 738.60

PROPOSED PGL PROFILE
+3.16%
-2.35%
℄ INTERSTATE ROUTE 88 STA. 6526+87.89
℄ RAMP A NB ℄ STA. 914+92.71
℄ RAMP B NB ℄ STA. 925+66.22
+10.44 EL. 715.02
+11.57 EL. 721.37
+08.61
+61.64
SN 022-2030 BRIDGE OMISSION
SSD = 653'
ex = -7.51%
K = 198
1,090.00' V.C.
ex = 0.05%
K = 233
100.00' V.C.
+70.00 EL. 724.18
+01.57 EL. 725.79
EXISTING PROFILE ALONG PROPOSED IL59 NB BASELINE
EXISTING GRADE EL.
PROPOSED GRADE EL.

913+00	914+00	915+00	916+00	917+00	918+00	919+00	920+00	921+00	922+00	923+00	924+00	925+00	926+00	927+00
714.76 / 714.69	716.21 / 716.27	717.71 / 717.85	719.19 / 719.43	720.41 / 721.01	722.05 / 722.55	722.46 / 723.97	723.29 / 725.27	721.84 / 726.43	717.92 / 727.47	716.26 / 728.39	717.13 / 729.18	718.72 / 729.84	712.72 / 730.37	706.65 / 730.78	706.60 / 731.06	706.19 / 731.22	716.58 / 731.25	718.04 / 731.15	719.81 / 730.93	720.12 / 730.58	722.76 / 730.10	727.22 / 729.50	727.15 / 728.77	726.96 / 727.92	726.94 / 726.94	725.62 / 725.83	724.71 / 724.65	723.74 / 723.50

PLAN: SURVEYED, PLOTTED, ALIGNMENT CHECKED, RT. OF WAY CHECKED, CADD FILE NAME, NOTE BOOK, NO.
PROFILE: SURVEYED, PLOTTED, GRADES CHECKED, B.M. NOTED, STRUCTURE NOTATNS CHKD, NOTE BOOK, NO.
DATE / BY

FILE NAME = $FILE$	USER NAME = $USER$	DESIGNED PJO	REVISED -
		DRAWN KES	REVISED -
	PLOT SCALE = $SCALE$	CHECKED JCM	REVISED -
	PLOT DATE = $DATE$	DATE 10/15/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE – ILLINOIS ROUTE 59 (NB)

SCALE: AS SHOWN | SHEET NO. 2 OF 18 SHEETS | STA. 913+00 TO STA. 927+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-5	DUPAGE	963	246
		CONTRACT NO. 60I31		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		