

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				URBAN		80% FED. / 20% STATE	80% FED/ 15% STATE / 5% LEMONT	<del>80% FED/ 15% STATE / 5% LEMONT</del>	100% LEMONT	<del>100% LEMONT</del>	<del>100% LEMONT</del>
				ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNAL INTERCONNECT	SAFETY	EMERGENCY VEHICLE PREEMPTION (EVP)	LOCAL		
0004	0021	<del>0021</del>	0021	<del>0021</del>	<del>0021</del>						
35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	1341	1341							
35501316	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	SQ YD	3298	3298							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8							
40600300	AGGREGATE (PRIME COAT)	TON	40	40							
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	978	978							
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	50	50							
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TONS	1405	1405							
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	99	99							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	396	396							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	12365				12,365			12365	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK, 6 INCH	SQ FT	334	334							
42400410	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	SQ FT	1234	1234							
42400800	DETECTABLE WARNINGS	SQ FT	134	134							
44000100	PAVEMENT REMOVAL	SQ YD	1380	1380							
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	7112	7112							

D:\ASSTEN\2012\12\18 - 155\County at Ashler Interchange - 60L79\60L79-155-500.dwg

Rev.

\* - DENOTES SPECIALTY ITEM

FILE NAME	USER NAME	DESIGNED	RG	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		DRAWN	RG	REVISED									1587	3098-R	COOK	95	5		
	PLT SCALE	CHECKED	MGR	REVISED															
	PLT DATE	DATE	MARCH, 2012	REVISED															
												SCALE:		SHEET NO. OF SHEETS		STA. TO STA.		CONTRACT NO. 60L79	
																		ILLINOIS FED. AID PROJECT	