

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				URBAN	80% FED. / 20% STATE	80% FED/ 15% STATE / 5% LEMONT	80% FED/ 15% STATE / 5% LEMONT	100% LEMONT	100% LEMONT	100% LEMONT	
				ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNAL INTERCONNECT	SAFETY	SAFETY	EMERGENCY VEHICLE PREEMPTION (EVP)	LOCAL	
87301732	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 20 3C	FOOT	467					467			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	80		80						
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	563		563						
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2		2						
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2						
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1						
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1						
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1						
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1		1						
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16						
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4						
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60		60						
87900200	DRILL EXISTING HANDHOLE	EACH	1		1						
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4		4						
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		4						
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	4		4						

Rev.

* - DENOTES SPECIALTY ITEM

FILE NAME: I:\6710-6712-18 - Asst. Intersectio... Eng\ASST\6710-6712-18\6712-18.dwg	USER NAME: rgnll	DESIGNED: RG	REVISIONS:	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE. 1587	SECTION 3098-R	COUNTY COOK	TOTAL SHEETS 95	SHEET NO. 12
PLANT SCALE: 1/8"=1'-0"	CHECKED: MGR	DATE: MARCH, 2012	REVISIONS:	SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 60L79					