

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				80% FED. 20% STATE	80% FED/ 15% STATE/ 5% LEMONT	80% FED/ 15% STATE/ 5% LEMONT	100% LEMONT	100% LEMONT	100% LEMONT		
				ROADWAY 0004	TRAFFIC SIGNALS 0021	TRAFFIC SIGNAL INTERCONNECT <del>0024</del>	SAFETY 0021	EMERGENCY VEHICLE PREEMPTION (EVP) <del>0024</del>	LOCAL <del>0021</del>		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1							
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	8496	8496							
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	54	54							
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	1600		1600						
Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	573	573							
Z0004538	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 10"	SQ YD	290	290							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	191	191							
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4				4				
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	65	65							
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	12	12							
Z0056614	STORM SEWER (WATER MAIN REQUIREMENTS) 21 INCH	FOOT	95	95							
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	294	294							
Z0076600	TRAINEES	HOOR									

Rev. - DENOTES SPECIALTY ITEM

FILE NAME	USER NAME	DESIGNED - RG	REVISIONS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - RG	REVISIONS		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	COOK	95	14	
		CHECKED - MGR	REVISIONS								CONTRACT NO. 60L79		
		DATE - MARCH, 2012	REVISIONS							ILLINOIS FED. AID PROJECT			