

SUMMARY OF QUANTITIES			85% FL	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			85% FL	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	85% FED. 15% STATE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	85% FED. 15% STATE 0005					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8250	8250					
67100100	MOBILIZATION	L SUM	1	1					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	930	930					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	320	320					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	230	230					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	190	190					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4080	4080					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	365	365					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	108.9	108.9					* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	365	365					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8250	8250					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	719	719					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	930	930					X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	103	103					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	320	320					X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	600	600					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	230	230					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	23	23					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	190	190					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2170	2170					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	370	370					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	58	58					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	108.9	108.9					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					

* SPECIALTY ITEMS
 Δ NON-PARTICIPATING (100%)

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
cdm_wor1sp10010010000000245100-000001-st-plot.dgn	mltronds	-	-
PLOT SCALE :	CHECKED :	DATE :	REVISED :
100,0000' = 1"	-	-	-
PLOT DATE :			
10/17/2012			

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	2010-06-RS	COOK	24	4
CONTRACT NO. 60L99				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				