

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	85% FED. 15% STATE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	85% FED. 15% STATE 0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	50 YD	25	25					44201757	CLASS D PATCHES, TYPE III, 9 INCH	50 YD	15	15				
25200110	SODDING, SALT TOLERANT	50 YD	25	25					48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	515	515				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	28	28					56109210	WATER VALVES TO BE ADJUSTED	EACH	4	4				
40600300	AGGREGATE (PRIME COAT)	TON	136	136					63500310	REMOVE AND REINSTALL DELINEATORS	EACH	28	28				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	51	51					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	50 YD	310	310					67100100	MOBILIZATION	L SUM	1	1				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	35	35					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	3800	3800					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	3800	3800					70300100	SHORT TERM PAVEMENT MARKING	FOOT	2480	2480				
42001300	PROTECTIVE COAT	50 YD	34	34					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	50 FT	76.6	76.6				
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	50 YD	32439	32439					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	27520	27520				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	50 YD	150	150					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	160	160				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	50 YD	110	110					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	410	410				

* SPECIALTY ITEMS
 NON-PARTICIPATING ITEMS

FILE NAME #FILE#	USER NAME #USER#	DESIGNED DRAWN	REVISIONS REVISIONS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES RIDGE ROAD & MARGARET STREET--IL 1 (HALSTED ST.) TO SCHWAB ST.				P. ALL RTE. 1620	SECTION 44-RS-2	COUNTY COOK	TOTAL SHEETS 30	SHEET NO. 3
PLOT SCALE #SCALE#		CHECKED DATE	REVISIONS REVISIONS	SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					