INDEX OF SHEETS

SHEET DESCRIPTION

- 1 COVER SHEET
- 2 INDEX, GENERAL NOTES AND HIGHWAY STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4 TYPICAL SECTIONS
- 5 ROADWAY AND PAVEMENT MARKING PLANS
- 6 CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT (BD24)
- 7 BUTT JOINTS AND BITUMINOUS TAPER (BD32)
- 8 HMA TAPER AT EDGE OF P. C. C. PAVEMENT (8033)
- 9 TRAFFIC CONTROL AND PROTECTION FOR SIDEROADS, INTERSECTIONS AND DRIVEWAYS (TC10)
- 10 DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC13)
- 11 ARTERIAL ROAD INFORMATION SIGN (TC22)

HIGHWAY STANDARDS

STD. NO. TITLE

442201-03CLASS C AND D PATCHES

606001-05CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER

701006-040FF-ROAD OPERATIONS, 2L. 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE

701011-03 OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY

701301-04 LANE CLOSURE, 2L. 2W. SHORT TIME OPERATIONS

701501-06-URBAN LANE CLOSURE, 2L. 2W. UNDIVIDED

701901-03TRAFFIC CONTROL DEVICES

780001-03TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

- 1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J. U. L. I. E." AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- 2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
- 3. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- 4. WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC THE MAXIMUM GRADE DIFFERENTIAL

 BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1 1/2 INCHES (40 MM)

 WHERE THE SPEED LIMIT IS 45 MPH (80 KM/H) OR LESS AND 1 INCH (25 MM) WHERE THE

 SPEED LIMIT IS GREATER THAN 45 MPH (80 KM/H). WITH WRITTEN APPROVAL FROM THE

 ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES (75 MM) MAY BE ALLOWED IF

 THE EDGE OF THE MILLING IS SLOPED A MINIMUM 1: 3 (V: H).
- 5. BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE
 RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND
 HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.
- 6. THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470

 A MINIMUM 72 HOURS IN ADVANCE OF BEGINNING WORK.
- 7. THE RESIDENT ENGINEER SHALL CONTACT DON CHIARUGI, AREA TRAFFIC FIELD ENGINEER,
 AT 847-741-9857 AT LEAST (2) WEEKS PRIOR TO PLACING PERMANENT PAVEMENT
 MARKINGS.
- 8. FERTILIZER NUTRIENTS FOR SODDING WILL BE ACCORDING TO SECTION 252 OF THE STANDARD SPECIFICATIONS. THE WORK WILL NOT BE PAID FOR SEPARATELY BUT INCLUDED IN THE COST OF SODDING.

USER NAME = 1485	DESIGNED	÷	EF	REVISED	•
	DRAWN	-	EF	REVISED	•
PLOT SCALE . 188.8888 '/ 12	CHECKED	•	RS	REVISED	-
PLOT DATE + 10/15/2012	DATE	-	10-23-2012	REVISED	•