

NOTE:

- SIGN SHALL BE RE-ERECTED ACCORDING TO ARTICLE 107.25 OF THE STANDARD SPECIFICATION (PROTECTION AND RESTORATION OF TRAFFIC SIGNS). ADDITIONAL SIGNS THAT HAVE NOT BEEN SURVEYED BUT ARE OBSCURED BY CONSTRUCTION OPERATIONS SHALL ALSO BE RE-ERECTED ACCORDING TO ARTICLE 107.25.
- ALL EXISTING PRIVATE SIGNS WITHIN THE STATE ROW THAT INTERFERE WITH CONSTRUCTION OPERATIONS WILL BE REMOVED AND REPLACED BY OTHERS. THE CONTRACTOR SHALL NOTIFY THE OWNERS PRIOR TO THE START OF CONSTRUCTION.
- EXISTING SIGN PANEL AND ASSEMBLY TO BE REMOVED SHALL BE DELIVERED TO AN IDOT MAINTENANCE YARD SPECIFIED BY THE ENGINEER.

| EXISTING SIGN NUMBER | PANEL DESCRIPTION | SIGN SUPPORT | STATION | OFFSET | FACING TRAFFIC | ACTION | DIMENSION W x H |
|--|---|--------------------------------|---------|--------|----------------|--|-----------------|
| E6-4 | (SHARED POST) | CIRCULAR POST MOUNTED (GROUND) | 691+15 | 36.9' | LT | SIGN PANEL ASSEMBLY TO BE RELOCATED | |
| E6-4a | CHAPEL HILL LN | | | | SB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 36" x 10" |
| E6-4b | STOP SIGN | | | | SB | SIGN PANEL TO BE REMOVED | 30" x 30" |
| E6-5 | SCHOOL CROSSING | POST MOUNTED (GROUND) | 691+18 | 22.7' | RT | SIGN PANEL ASSEMBLY TO BE RELOCATED | 36" x 36" |
| E6-6 | (SHARED POST) | POST MOUNTED (GROUND) | 691+46 | 56.5' | LT | SIGN PANEL ASSEMBLY TO BE RELOCATED | |
| E6-6a | NO OUTLET | | | | NB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 33" x 33" |
| E6-6b | SLOW CHILDREN | | | | NB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 18" x 24" |
| WILLOW ROAD (STA 693+00 TO STA 704+00) | | | | | | | |
| E7-1 | RED LIGHT PHOTO ENFORCED | WOOD POST MOUNTED (GROUND) | 694+99 | 24.6' | RT | SIGN PANEL ASSEMBLY TO BE REMOVED BY OTHERS | 36" x 36" |
| E7-2 | NORTHFIELD COMMUNITY NURSERY SCHOOL | DUAL POST MOUNTED (GROUND) | 695+59 | 67.7' | LT | SIGN AND POST TO REMAIN | 66" x 30" |
| E7-3 | SPEED LIMIT 35 | POST MOUNTED (GROUND) | 695+61 | 32.5' | LT | SIGN PANEL ASSEMBLY TO BE REMOVED | 30" x 36" |
| E7-4 | NORTHFIELD COMMUNITY CHURCH | STONE BASE | 696+13 | 65.8' | LT | SIGN AND POST TO REMAIN | 128" x 79" |
| E7-5 | FOLDED STOP SIGN | MOUNTED ON SIGNAL POST | 696+30 | 27.5' | RT | SIGN PANEL TO BE RELOCATED ON NEW SIGNAL POST | 30" x 30" |
| E7-6 | (SHARED POST) | MOUNTED ON SIGNAL POST | 696+31 | 47.1' | LT | SIGN PANEL ASSEMBLY TO BE RELOCATED ON NEW SIGNAL POST | |
| E7-6a | RED LIGHT PHOTO ENFORCED | | | | WB | SIGN PANEL TO BE REMOVED BY OTHERS | 30" x 30" |
| E7-6b | NO TURN ON RED | | | | WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 24" |
| E7-6c | ON SCHOOL DAY WHEN CHILDREN ARE PRESENT | | | | WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 12" |
| E7-7 | (SHARED POST) | MOUNTED ON SIGNAL POST | 696+42 | 47.3' | LT | SIGN PANEL ASSEMBLY TO BE RELOCATED ON NEW SIGNAL POST | |
| E7-7a | NO TURN ON RED | | | | SB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 24" |
| E7-7b | ON SCHOOL DAY WHEN CHILDREN ARE PRESENT | | | | SB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 12" |
| E7-7c | FOLDED STOP SIGN | | | | SB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 30" x 30" |
| E7-8 | SPEED LIMIT 35 | DUAL POST MOUNTED (GROUND) | 696+46 | 105.5' | RT | SIGN PANEL ASSEMBLY TO BE RELOCATED | 30" x 36" |
| E7-9 | NO PARKING THIS SIDE OF STREET | POST MOUNTED (GROUND) | 696+49 | 143.6' | LT | SIGN AND POST TO REMAIN | 12" x 18" |
| E7-10 | (SHARED POST) | POST MOUNTED (GROUND) | 696+95 | 74.3' | RT | SIGN PANEL ASSEMBLY TO BE RELOCATED | |
| E7-10a | SCHOOL CROSSING | | | | NB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 36" x 36" |
| E7-10b | AHEAD | | | | NB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 12" |
| E7-11 | SCHOOL SPEED LIMIT 20 | POST MOUNTED (GROUND) | 696+96 | 136.6' | LT | SIGN AND POST TO REMAIN | 24" x 48" |
| E7-12 | (SHARED POST) | MOUNTED ON SIGNAL POST | 696+96 | 54.3' | RT | SIGN PANEL ASSEMBLY TO BE RELOCATED ON NEW SIGNAL POST | |
| E7-12a | NO TURN ON RED | | | | NB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 24" |
| E7-12b | FOLDED STOP SIGN | | | | NB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 30" x 30" |
| E7-13 | SPEED LIMIT 20 | POST MOUNTED (GROUND) | 696+97 | 94.6' | LT | SIGN PANEL ASSEMBLY TO BE RELOCATED | 18" x 24" |
| E7-14 | (SHARED POST) | MOUNTED ON SIGNAL POST | 697+00 | 51.3' | LT | SIGN PANEL ASSEMBLY TO BE REMOVED | |
| E7-14a | NO TURN ON RED | | | | NB | SIGN PANEL TO BE REMOVED WITH ASSEMBLY | 24" x 24" |
| E7-14b | ON SCHOOL DAY WHEN CHILDREN ARE PRESENT | | | | NB | SIGN PANEL TO BE REMOVED WITH ASSEMBLY | 24" x 12" |
| E7-15 | (SHARED POST) | MOUNTED ON SIGNAL POST | 697+13 | 36.9' | RT | SIGN PANEL ASSEMBLY TO BE REMOVED | |
| E7-15a | WAGNER RD | | | | EB | SIGN PANEL TO BE REMOVED WITH ASSEMBLY | 44" x 18" |
| E7-15b | RED LIGHT PHOTO ENFORCED | | | | EB | SIGN PANEL TO BE REMOVED BY OTHERS | 36" x 36" |
| E7-16 | (SHARED POST) | MOUNTED ON SIGNAL POST | 697+15 | 36.9' | LT | SIGN PANEL ASSEMBLY TO BE RELOCATED ON NEW SIGNAL POST | |
| E7-16a | NO TURN ON RED | | | | WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 24" |
| E7-16b | ON SCHOOL DAY WHEN CHILDREN ARE PRESENT | | | | WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 12" |
| E7-16c | FOLDED STOP SIGN | | | | WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 30" x 30" |
| E7-17 | (SHARED POST) | POST MOUNTED (GROUND) | 697+19 | 32.5' | LT | SIGN PANEL ASSEMBLY TO BE RELOCATED | |
| E7-17a | SCHOOL CROSSING | | | | WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 36" x 36" |
| E7-17b | ARROW | | | | WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 21" x 15" |
| E7-17c | STOP HERE ON RED | | | | WB | SIGN PANEL TO BE REMOVED | 24" x 30" |
| E7-18 | (SHARED POST) | POST MOUNTED (GROUND) | 697+20 | 26.8' | RT | SIGN PANEL ASSEMBLY TO BE RELOCATED ON NEW SIGNAL POST | |
| E7-18a | SCHOOL CROSSING | | | | EB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 36" x 36" |
| E7-18b | ARROW | | | | EB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 21" x 15" |
| E7-19 | WILLOW PARK | DUAL STONE POSTS | 697+45 | 57.0' | LT | SIGN AND POST TO REMAIN | 58" x 21" |
| E7-20 | (SHARED POST) | POST MOUNTED (GROUND) | 698+28 | 23.8' | RT | SIGN PANEL ASSEMBLY TO BE REMOVED | |
| E7-20a | SPEED LIMIT 35 | | | | EB | SIGN PANEL TO BE REMOVED WITH ASSEMBLY | 30" x 36" |
| E7-20b | NO PARKING ANY TIME | | | | EB | SIGN PANEL TO BE REMOVED WITH ASSEMBLY | 12" x 18" |
| E7-21 | NO PARKING ANY TIME | CIRCULAR POST MOUNTED (GROUND) | 698+31 | 35.5' | LT | SIGN PANEL ASSEMBLY TO BE REMOVED | 12" x 18" |
| E7-22 | RED LIGHT PHOTO ENFORCED | WOOD POST MOUNTED (GROUND) | 698+47 | 31.4' | LT | SIGN PANEL ASSEMBLY TO BE REMOVED BY OTHERS | 36" x 36" |
| E7-23 | NO PARKING ANY TIME | CIRCULAR POST MOUNTED (GROUND) | 699+71 | 32.4' | LT | SIGN PANEL ASSEMBLY TO BE REMOVED | 12" x 18" |
| E7-24 | (SHARED POST) | POST MOUNTED (GROUND) | 699+77 | 29.5' | RT | SIGN PANEL ASSEMBLY TO BE RELOCATED | |
| E7-24a | WILLOW RD (2 SIGN PANELS BACK TO BACK) | | | | NB/SB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 10" |
| E7-24b | EATON ST (2 SIGN PANELS BACK TO BACK) | | | | EB/WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 24" x 10" |
| E7-25 | SPEED LIMIT 20 | POST MOUNTED (GROUND) | 699+89 | 76.4' | RT | SIGN PANEL ASSEMBLY TO BE RELOCATED | 24" x 30" |
| E7-26 | STOP SIGN | POST MOUNTED (GROUND) | 700+19 | 54.2' | RT | SIGN PANEL ASSEMBLY TO BE RELOCATED | 30" x 30" |
| E7-27 | (SHARED POST) | POST MOUNTED (GROUND) | 701+56 | 24.7' | LT | SIGN PANEL ASSEMBLY TO BE RELOCATED | |
| E7-27a | SCHOOL CROSSING | | | | WB | SIGN PANEL TO BE RELOCATED WITH ASSEMBLY | 36" x 36" |
| E7-27b | NO PARKING ANY TIME | | | | WB | SIGN PANEL TO BE REMOVED | 12" x 18" |
| E7-28 | NO PARKING ANY TIME | POST MOUNTED (GROUND) | 701+60 | 24.5' | RT | SIGN PANEL ASSEMBLY TO BE REMOVED | 12" x 18" |
| E7-29 | WARNING UNDERGROUND CABLE | POST MOUNTED (GROUND) | 702+02 | 37.9' | LT | SIGN PANEL ASSEMBLY TO BE REMOVED BY OTHERS | 4" x 8" |