

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 5% STATE 5% CITY OF CALUMET 0021	TRAFFIC INTER- CONNECT 100% STATE 0021	TRAFFIC EVP 100% CITY OF CALUMET 0021			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 5% STATE 5% CITY OF CALUMET 0021	TRAFFIC INTER- CONNECT 100% STATE 0021	TRAFFIC EVP 100% CITY OF CALUMET 0021		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	3.8	3.8						44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	157	157					
25200110	SODDING, SALT TOLERANT	SO YD	3.8	3.8						44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	9626	9626					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	11						44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	92	92					
40600300	AGGREGATE (PRIME COAT)	TON	26	26						44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	92	92					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20						44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	105	105					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	547	547						60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE I FRAME, CLOSED LID	EACH	1	1					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	184	184					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	969	969						67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	35	35						67100100	MOBILIZATION	L SUM	1	1					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1276	1276						70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1					
42001300	PROTECTIVE COAT	SO YD	206	206						70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1300	1300						70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	13014	13014						70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	184	184						70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
44000600	SIDEWALK REMOVAL	SO FT	1300	1300															

* SPECIALTY ITEMS

FILE NAME: c:\p\work\p100\hardcopy\0208304\PII\12-11-10\12-11-10.dgn	USER NAME: hars2001	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BURNHAM AVE AT RIVER OAKS DR SUMMARY OF QUANTITIES		F.A.U. RTE. 2943	SECTION 3162A-N-1	COUNTY COOK	TOTAL SHEETS 42	SHEET NO. 4
PLOT SCALE: 1/8" = 1'-0"	CHECKED: -	REVISED: -	SCALE: 1" = 100'-0"		SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		CONTRACT NO. 60147		
PLOT DATE: 10/22/2012	DATE: -	REVISED: -									