

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 5% STATE 5% CITY OF CALUMET 0021	TRAFFIC INTER- CONNECT 100% STATE 0021	TRAFFIC EVP 100% CITY OF CALUMET 0021			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 5% STATE 5% CITY OF CALUMET 0021	TRAFFIC INTER- CONNECT 100% STATE 0021	TRAFFIC EVP 100% CITY OF CALUMET 0021		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						* 80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1		1				
* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	2909	2909						* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1940		1650	290			
* 70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	600	600						* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	57		57				
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7647	7647						* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	53		53				
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1038	1038						* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	370		370				
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	101	101						* 81400100	HANDHOLE	EACH	7		7				
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	175	175						* 81400200	HEAVY-DUTY HANDHOLE	EACH	4		4				
* 72000100	SIGN PANEL - TYPE 1	SO FT	37.5	37.5						* 81400300	DOUBLE HANDHOLE	EACH	1		1				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	602.5	602.5						* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7647	7647						* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1038	1038						* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2232				2232		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	101	101						* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1340		1340				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175						* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1710		1710				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	194	194						* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2080		2080				
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	184	184						* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1820		1820				

\* SPECIALTY ITEMS

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				BURNHAM AVE AT RIVER OAKS DR SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ORIG. WORK PLOTTED FROM		DRAWN	REVISED									2943	3162A-N-1	COOK	42	5
PLOT SCALE		CHECKED	REVISED									CONTRACT NO. 60747				
PLOT DATE		DATE	REVISED									FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				