

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 5% STATE 5% CITY OF CALUMET 0021	TRAFFIC INTER- CONNECT 100% STATE 0021	TRAFFIC EVP 100% CITY OF CALUMET 0021			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FEDERAL 10% STATE 0004	TRAFFIC 90% FEDERAL 5% STATE 5% CITY OF CALUMET 0021	TRAFFIC INTER- CONNECT 100% STATE 0021	TRAFFIC EVP 100% CITY OF CALUMET 0021		
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3566		3566					* 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1				
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	190		190					* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	3		3				
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	802		802					* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8		8				
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1		1					* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12		12				
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		4					* 88500100	INDUCTIVE LOOP DETECTOR	EACH	11		11				
* 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1					* 88600100	DETECTOR LOOP, TYPE I	FOOT	680		680				
* 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1					* 88700200	LIGHT DETECTOR	EACH	2				2		
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1					* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1				1		
* 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1					* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8		8				
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20		20					* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1				
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4					* 89502200	MODIFY EXISTING CONTROLLER	EACH	1		1				
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	48		48					* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5140		5140				
* 87900200	DRILL EXISTING HANDHOLE	EACH	1			1				* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1				
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	7		7					* 89502380	REMOVE EXISTING HANDHOLE	EACH	7		7				
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5		5					* 89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	1		1				

\* SPECIALTY ITEMS

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
o:\p\work\p100\hamzah\20206304\PI412-111-11\p100.dgn	hamzah	DRAWN :	REVISED :
		CHECKED :	REVISED :
		DATE :	REVISED :

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

BURNHAM AVE AT RIVER OAKS DR  
SUMMARY OF QUANTITIES

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.I. RTE. 2943	SECTION 3162A-N-1	COUNTY COOK	TOTAL SHEETS 42	SHEET NO. 6
			CONTRACT NO. 6047				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							