

MOT LEGEND

	WORK ZONE
	TEMPORARY PAVEMENT CONSTRUCTED IN PREVIOUS STAGING
	TEMPORARY PAVEMENT TO BE CONSTRUCTED (SEE NOTE 1 BELOW)
	COMPLETED PAVEMENT
	ARROW BOARD
	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, Z0030250), 18 BARRELS
	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, Z0030250), 9 BARRELS
	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW, Z0030260)
	DIRECTION OF TRAFFIC
	TEMPORARY CONCRETE BARRIER (70400100)
	CONSTRUCTION SIGN PER IDOT STANDARDS UNLESS NOTED
	TYPE III BARRICADE WITH STEADY BURNING LIGHT
	CONE, DRUM OR BARRICADE
	AMBER FLASHING LIGHT

- (A) TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS (70300210) (SOLID WHITE)
- (B) TEMPORARY PAVEMENT MARKING - LINE 4" (70300220) (SOLID YELLOW)
- (C) TEMPORARY PAVEMENT MARKING - LINE 4" (70300220) (SOLID WHITE)
- (D) TEMPORARY PAVEMENT MARKING - LINE 4" (70300220) (SKIP-DASH, WHITE, 10' DASH, 30' SKIP)
- (E) TEMPORARY PAVEMENT MARKING - LINE 6" (70300220) (SKIP-DASH, WHITE, 2' DASH, 6' SKIP)
- (F) TEMPORARY PAVEMENT MARKING - LINE 4" (70300220) (DOUBLE SOLID YELLOW - 11" C-C SPACING)
- (G) TEMPORARY PAVEMENT MARKING - LINE 6" (70300240) (SOLID WHITE)
- (H) TEMPORARY PAVEMENT MARKING - LINE 12" (70300260) (SOLID WHITE)
- (I) TEMPORARY PAVEMENT MARKING - LINE 24" (70300280) (SOLID WHITE)
- (J) TEMPORARY PAVEMENT MARKING - LINE 4" (70300220) (SKIP-DASH, YELLOW, 10' DASH, 30' SKIP)
- (K) TEMPORARY PAVEMENT MARKING - LINE 12" (70300260) (SOLID YELLOW)
- (L) TEMPORARY PAVEMENT MARKING - LINE 4" (70300220) (SKIP-DASH, YELLOW, 2' DASH, 6' SKIP)

①		R8-8 24" x 30"
②		R10-11a 24" x 30"
③		R10-6a 36" x 42"
④		W10-1
		W10-15P

NOTE:

1. FULL-DEPTH TEMPORARY PAVEMENT THICKNESS SHALL BE 12" OF HOT-MIX ASPHALT OR 10" OF PCC MEETING THE MIXTURE REQUIREMENTS AS SET FORTH IN THE HMA MIXTURE REQUIREMENTS TABLE ON SHEET 20 .

USER NAME = user	DESIGNED - JJS	REVISED -
	DRAWN - ML	REVISED -
PLOT SCALE = *SCALE*	CHECKED - LGP	REVISED -
PLOT DATE = 11/2/2012	DATE - 08-03-2012	REVISED -

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	32 WRS-5	DUPAGE	388	54
CONTRACT NO. 60B42				
ILLINOIS FED. AID PROJECT				