



BORDER
R=1.5"
TH=0.63"
IN=0.47"

NOTES:

1. FOR SIGNS, USE BLACK LETTERING ON ORANGE BACKGROUND.
2. SIGNS SHALL BE INSTALLED WITHIN TOLLWAY OR IDOT RIGHT-OF-WAY, WITH A MINIMUM SPACING OF 400 FEET FROM OTHER GUIDE SIGNS, AND 200 FEET FROM ALL OTHER SIGNS
3. CONTRACTOR SHALL INSTALL SIGNING ONCE PROPOSED CPR BRIDGE BEAMS ARE ERECTED IN STAGE 2, OR AS DIRECTED BY THE ENGINEER.
4. SEE SPECIAL PROVISIONS FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION
5. ONE SIGN ASSEMBLY EQUALS 49.5 SQ. FT.
6. SIGNS, POSTS, AND MOUNTING BRACKETS SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.
7. LOCATIONS ARE APPROXIMATE. EXACT LOCATIONS TO BE FIELD VERIFIED AND APPROVED BY THE ENGINEER.

ALL DIMENSIONS ARE IN INCHES
UNLESS OTHERWISE SHOWN.

 HDR HDR ENGINEERING, INC.	USER NAME = user	DESIGNED - JJS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MOT DETAIL- ADVANCE WARNING SIGNS			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = *SCALE*	CHECKED - LGP	REVISED -		SCALE: NTS	SHEET NO. 25 OF 29 SHEETS	STA.	TO STA.	1321	32VB	DUPAGE	388
PLOT DATE = 11/21/2012	DATE - 11-20-2012	REVISED -	REVISED -				CONTRACT NO. 60W01			ILLINOIS FED. AID PROJECT		