## <u>LEGEND</u>

EXISTING LIGHTING UNIT TO REMAIN 40' M.H., 12' M.A., 310W, 120V HPS LUMINAIRE CITY OF NAPERVILLE O—EN

EXISTING LIGHTING UNIT TO BE REMOVED AND RELOCATED 40' M.H., 12' M.A., 310W, 120V HPS LUMINAIRE

CITY OF NAPERVILLE

O—RRN

EXISTING LIGHTING CONTROLLER CABINET, SINGLE DOOR, CONSOLE TYPE, 100A, 120/240V, 1Ø CITY OF NAPERVILLE MAINTAINEO

EXISTING LIGHTING HANDHOLE TO BE REMOVED

## NOTES:

- THE CONTRACTOR SHALL NOT DE-ENERGIZE, DISCONNECT, OR REMOVE ANY EXISTING LIGHTING EQUIPMENT UNLESS A REPLACEMENT EQUIPMENT IS IN PLACE AND MADE OPERATIONAL BEFORE THE EXISTING EQUIPMENT CAN BE TAKEN OUT OF SERVICE.
- NEW LOCATIONS OF ALL RELOCATED LIGHTING EQUIPMENT ARE SHOWN ON THE TEMPORARY AND PROPOSED LIGHTING PLANS.
- 3. INSTALL RELOCATED EXISTING LIGHTING CONTROLLER CABINETS ON NEW FOUNDATIONS.
- THE CONTRACTOR SHALL PROPERLY HANDLE AND DELIVER ALL REMOVED LIGHTING EQUIPMENT THAT WILL NOT BE REUSED TO THE OWNER'S PUBLIC WORKS DEPARTMENT DESIGNATED STORAGE/MAINTENANCE YARD. ALL COSTS RELATED TO REMOVAL, HANDLING, AND TRANSPORTATION OF THE REMOVED EQUIPMENT SHALL BE INCLUDED IN THE COST OF THE ITEM BEING REMOVED.
- EXISTING WIRES AND CABLES THAT WILL NOT BE REUSED SHALL BE ABANDONED IN PLACE OR REMOVED BY THE CONTRACTOR AND DISPOSED OF OUTSIDE THE RIGHT OF WAY AT HIS OWN EXPENSE.

