(175)

68 (1700)

54 (1350)

## NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.

SCALE: NONE

- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

YRIGHT © 2012 ENGINEERING ENTERPRISES, INC.

RIGHT © 2012 ENGINEERING ENTERPRISES, INC.										
NAME =	USER NAME = gaglienobt	DESIGNED -	REVISED	- R. MIRS 09-15-97						
:ststd\22x34\tc22.dgn		DRAWN -	REVISED	- R. WIRS 12-11-97						
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED	T. RAMMACHER 02-02-99						
	PLOT DATÉ = 1/4/2008	DATE -	REVISED	- C. JUCIUS 01-31-07						

										Ġ,
ARTERIAL ROAD			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	報		
INFORMATION SIGN				3553	10-00031-00-RS	DUPAGE	29	26	2	
her constructed older				TC-22		CONTRACT	NO. 6	3758		
<u> </u>	SHEET NO. 1 OF 1	SHEETS	STA.	TO STA.	FEO. ROAD DIST, NO. 1   ILLINOIS FED. AID PROJECT - M-9003(866)					i