

PAVEMENT MARKING SCHEDULE										
LOCATION		DISTANCE	PAINT PVT MK 4"	PAINT PVT MK 6"	TEMP MARK 4"	TEMP MARK 6"	SHORT-TERM MARK	WORK ZONE PAVT MARK REM	RAISED REFLECTIVE PVMT MARKERS	REMOVAL RAISED REFLECTIVE PVT MARKERS
STA		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO. FT.	EACH	EACH
027-0072										
1738+25	TO 1745+00	675	1350	169	1350	169	203	22	8	8
(2) DOUBLE APPLICATION			1350	169						
027-0072 SUBTOTAL			2700	338	1350	169	203	22	8	8
027-0073										
1590+50	TO 1597+95	745	1490	186	1490	186	224	25	9	9
(2) DOUBLE APPLICATION			1490	186						
027-0073 SUBTOTAL			2980	373	1490	186	224	25	9	9
GRAND TOTAL		1420	5680	710	2840	355	426	47	18	18

(1) R.E. TO VERIFY NO PASSING ZONES PRIOR TO MILLING OPERATION
(2) PAINT MUST BE DONE IN A DOUBLE APPLICATION

PAVEMENT REMOVAL AND BR APPR PVT CONN SCHEDULE					
STA. TO STA.	LENGTH	AREA	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	HMA SURFACE REMOVAL VARIABLE DEPTH	PAVEMENT REMOVAL
FORD COUNTY		FT	SO YD	SO YD	SO YD
SN 027-0072					
1738+25	1739+15	90		240	
1744+10	1745+00	90		240	
1740+52	1740+58	6	21.3		
1740+58	1740+88	30			101.3
1742+20	1742+26	6	21.3		
1741+90	1742+20	30			101.3
SUBTOTAL		180	480	42.7	202.7
SN 027-0073					
1590+95	1592+15	120		320	
1596+98	1597+95	97		259	
1593+20	1593+26	6	21.3		
1593+26	1593+56	30			101.3
1594+33	1594+39	6	21.3		
1594+39	1594+69	30			101.3
SUBTOTAL		217	579	42.7	202.7
GRAND TOTALS			85	1059	405

R.O.W. MARKERS	
LOCATION	FURNISH AND ERECT ROW MARKERS
027-0072	EACH
STA 1738+18 85' RT	1
STA 1738+22 85' LT	1
STA 1738+88.68 60' RT	1
STA 1738+91.49 60' LT	1
STA 1740+78.60 60' RT	1
STA 1744+00 60' LT	1
STA 1745+00 30.92' LT	1
027-0073	
STA 1590+50 30' RT	1
STA 1590+50 30' LT	1
STA 1591+50 60' RT	1
STA 1591+50 60' LT	1
STA 1597+00 60' RT	1
STA 1597+00 60' LT	1
STA 1598+00 30' RT	1
STA 1598+00 30' LT	1
GRAND TOTAL	15