

80/20 FED/ST

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY 0001 RURAL	BRIDGE 0008 S.N. 036-0062, 0063	BRIDGE 0008 S.N. 036-0065	HIGHWAY LIGHTING 0021 RURAL
				LOSEC,01	LOSEC, 01	LOSEC,02	LOSEC,01
60223700	MANHOLES, TYPE A, 6"-DIAMETER, TYPE I FRAME, OPEN LID	EACH	1	1			
60223800	MANHOLES, TYPE A, 6"-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1	1			
60224066	MANHOLES, TYPE A, 6"-DIAMETER, WITH MEDIAN INLET (604101)	EACH	2	2			
60236200	INLETS, TYPE A, TYPE B GRATE	EACH	4	4			
60238305	INLETS, TYPE A, WITH MEDIAN INLET (604101)	EACH	1	1			
60246605	MEDIAN INLET (604101)	EACH	1	1			
60602500	CONCRETE GUTTER, TYPE A	FOOT	63	63			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	910	910			
60608552	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	177	177			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	1,466	1,466			
60618750	CONCRETE MEDIAN, TYPE M-4.06	SO FT	8,278	8,278			
60624600	CORRUGATED MEDIAN	SO FT	732	732			
60900515	CONCRETE THRUST BLOCKS	EACH	4	4			
61000225	TYPE F INLET BOX, STANDARD 610001	EACH	2	2			
61000335	TYPE C INLET BOX, STANDARD 610001	EACH	2	2			

• DENOTES SPECIALTY ITEM

FILE NAME : D:\68409-SHT-500.dgn	USER NAME : zschl	DESIGNED - OBS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES US ROUTE 34</b>			F.A.P. RTE. 313	SECTION 7-2 : 6-1	COUNTY HENDERSON	TOTAL SHEETS 976	SHEET NO. 19
	PLOT SCALE : 96.0000' / in.	DRAWN - PSBA	REVISED -		SCALE: N.A.	SHEET NO. 15 OF 25 SHEETS	STA.	TO STA.	CONTRACT NO. 68409			
	PLOT DATE : 10/16/2012	CHECKED - CSB	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE - 10/2012	REVISED -									