

PIPE UNDERDRAINS - SCHEDULE (1 OF 4)								
LOCATION STATION TO STATION		PIPE UNDERDRAINS 4"						NOTES
		WB O/S	WB I/S	EB I/S	EB O/S	LT	RT	
FROM	TO	FOOT						
US ROUTE 34								
532+00.00	537+00.00	500	500	500	500			
537+00.00	542+00.00	500	500	500	500			
542+00.00	547+00.00	500	500	500	500			
547+00.00	549+69.80	270	270	270	270			
549+69.80	553+00.00	330	330	330	330			
553+00.00	557+00.00	400	400	400	400			
557+00.00	562+00.00	500	500	500	500			
562+00.00	567+00.00	500	500	500	500			
567+00.00	572+00.00	500	500	500	500			
572+00.00	577+00.00	500	500	500	500			
577+00.00	581+50.00	450	450	450	450			
581+50.00	583+12.50	163	163	163	163			
583+12.50	586+37.50		325	325	325			
583+12.50	587+00.00	388						End WB O/S Underdrain, Connect Ramp D RT Underdrain
586+37.50	588+00.00		163	163	163			
588+00.00	592+00.00		400	400				
588+00.00	592+35.97				436			End EB O/S Underdrain, Connect to Ramp C RT Underdrain
592+00.00	597+00.00		500	500				
597+00.00	602+00.00		500	500				
598+95.97	602+00.00				304			Begin EB O/S Underdrain
599+03.85	602+00.00	296						Begin WB O/S Underdrain
602+00.00	606+00.00	400	400	400	400			
606+00.00	609+50.00	350	350	350				
602+00.00	609+50.00				750			
609+50.00	614+00.00	450	450	450	450			
614+00.00	618+00.00	400	400	400	400			
618+00.00	622+00.00	400	400	400	400			
622+00.00	622+82.37				82			End EB O/S Underdrain
622+00.00	627+00.00		500	500				
622+00.00	628+00.00	600						End WB O/S Underdrain, Connect to Media Inlet
627+00.00	632+00.00		500	500				
632+00.00	637+00.00		500	500				
632+59.42	637+00.00	441						Begin WB O/S Underdrain, Connect to Ramp A RT Underdrain
635+33.53	637+00.00				166			Begin EB O/S Underdrain, Connect to Ramp B RT Underdrain
637+00.00	642+00.00	500	500	500	500			
642+00.00	647+00.00	500	500	500	500			
647+00.00	652+00.0	500	500	500	500			
652+00.0	657+00.00	500	500	500	500			
657+00.00	662+00.00	500	500	500	500			
662+00.00	667+00.00	500	500	500	500			
667+00.00	672+00.00	500	500	500	500			
672+00.00	677+00.00	500	500	500	500			
677+00.00	678+50.00	150	150	150	150			
678+50.00	680+50.00	200	200	200	200			
SUBTOTAL 1		13,187	14,850	14,850	13,339	0	0	

LEGEND
WB O/S = WEST BOUND OUTSIDE
WB I/S = WEST BOUND INSIDE
EB O/S = EAST BOUND OUTSIDE
EB I/S = EAST BOUND INSIDE

FILE NAME = D468409-SHT-25-28-PIPE UNDERDRAINS.dgn	USER NAME = danw	DESIGNED - DBS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES US ROUTE 34			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 100.0000' / 1in.	CHECKED - CSB	REVISIED -	313					7-2 ; 6-1	HENDERSON	976	54	
PLOT DATE = 11/16/2012	DATE - 10/2012	REVISIED -	SCALE: N.A.			SHEET NO. 25 OF 51 SHEETS	STA.	TO STA.	CONTRACT NO. 68409			
ILLINOIS FED. AID PROJECT												