

PIPE UNDERDRAINS - SCHEDULE (2 OF 4)								
LOCATION STATION TO STATION		PIPE UNDERDRAINS 4"						NOTES
		WB O/S	WB I/S	EB I/S	EB O/S	LT	RT	
FROM	TO	FOOT						
US ROUTE 34 (CONTINUED)								
680+50.00	685+00.00	450	450	450	450			
685+00.00	690+00.00	500	500	500	500			
690+00.00	695+00.00	500	500	500	500			
695+00.00	698+37.50	338						
695+00.00	700+00.00		500	500	500			
698+37.50	700+00.00	163						
700+00.00	701+62.50	163	163	163	163			
701+62.50	703+25.00	163	163	163	163			
703+25.00	704+87.50	163	163	163	163			
704+87.50	708+12.50	325	325	325	325			
708+12.50	713+00.00	488	488	488	488			
713+00.00	718+00.00	500	500	500	500			
718+00.00	723+00.00	500	500	500	500			
723+00.00	728+00.00	500	500	500	500			
728+00.00	733+00.00	500	500	500	500			
733+00.00	738+00.00	500	500	500	500			
738+00.00	743+00.00	500	500	500	500			
743+00.00	748+00.00	500	500	500	500			
748+00.00	750+50.00	250	250	250	250			
750+50.00	753+00.00	250			250			
750+50.00	754+20.00		370	370				
753+00.00	755+35.00	235						End EB O/S Underdrain
753+00.00	755+40.00				240			End EB I/S Underdrain
754+20.00	755+40.00		120					End WB I/S Underdrain
754+20.00	755+45.00			125				End WB O/S Underdrain
759+10.00	759+30.00	20						Begin EB O/S Underdrain
759+15.00	759+30.00				15			Begin EB I/S Underdrain
759+15.00	759+30.00		15					Begin WB I/S Underdrain
759+20.00	759+30.00			10				Begin WB O/S Underdrain
759+30.00	764+00.00	470	470	470	470			
764+00.00	769+00.00	500	500	500	500			
769+00.00	774+00.00	500	500	500	500			
774+00.00	779+00.00	500	500	500	500			
779+00.00	784+00.00	500	500	500	500			
784+00.00	789+00.00	500	500	500	500			
789+00.00	794+00.00	500	500	500	500			
794+00.00	799+00.00	500	500	500	500			
799+00.00	802+30.00	330	330	330	330			
802+30.00	804+30.00	200	200	200	200			
804+30.00	807+00.00	270	270	270	270			End EB O/S and EB I/S Underdrains
807+00.00	810+00.00	300	300	300	300			End WB O/S and WB I/S Underdrains
SUBTOTAL 2		12,575	12,575	12,575	12,575	0	0	