

STONE RIPRAP SCHEDULE (1 OF 4)									
LOCATION				LENGTH	WIDTH	STONE RIPRAP, CLASS B3	STONE RIPRAP, CLASS B4	STONE RIPRAP, CLASS B5	FILTER FABRIC
FROM STA.	OFFSET	TO STA.	OFFSET	FT	FT		SO YD	SO YD	SO YD
US ROUTE 34									
514+60	RT	514+78	RT	20	25		56		56
516+36	LT	516+53	LT	20	20		44		44
520+56	RT	520+73	RT	24	20			53	53
521+68	LT	521+84	LT	60	16		107		107
523+00	LT	523+14	LT	20	10		22		22
524+90	LT	525+10	LT	20	20		44		44
527+52	LT	528+52	LT	100	20		222		222
529+35	LT	529+60	LT	25	25		69		69
529+74	RT	529+94	RT	20	20		44		44
537+22	RT	537+32	RT	38	10		42		42
539+90	RT	540+10	RT	20	20		44		44
550+70	LT	550+90	LT	75	22			183	183
550+97	LT	551+66	LT	70	16			124	124
551+66	LT	554+64	LT	300	16		533		533
552+89	RT	553+05	RT	20	20		44		44
554+64	LT	555+00	LT	36	30			120	120
555+94	LT	556+42	LT	55	30		183		183
556+43	RT	556+96	RT	50	20		111		111
568+81	LT	569+51	LT	70	23		179		179
570+13	RT	570+37	RT	24	18			48	48
604+73	RT	605+89	RT	120	10	133			
604+80	LT	605+90	LT	110	10	122			
605+90	LT	606+20	LT	30	30		100		100
605+89	RT	606+08	RT	20	20		44		44
610+30	LT	610+54	LT	24	24		64		64
612+74	LT	613+03	LT	28	26		81		81
621+37	LT	621+55	LT	20	20		44		44
621+55	LT	622+57	LT	105	10	117			
627+94	LT	628+14	LT	20	20	44			
628+36	RT	628+56	RT	55	20		122		122
635+23	RT	635+43	RT	55	20	122			
639+49	RT	639+69	RT	45	20	100			
642+00	RT	642+25	RT	80	14	124			
643+15	RT	643+79	RT	45	35			175	175
643+32	LT	643+57	LT	50	36			200	200
646+10	RT	646+30	RT	20	20	44			
654+20	RT	654+40	RT	30	20	67			
660+44	RT	660+64	RT	20	23	51			
660+97	RT	661+17	RT	20	20	44			
662+97	RT	663+17	RT	40	20		89		89
663+10	LT	663+35	LT	5	25		14		14
663+10	LT	663+35	LT	28	25		78		78
663+10	LT	663+35	LT	16	25	44			
667+80	LT	668+00	LT	20	10	22			
668+00	RT	669+42	RT	147	10	163			
SUBTOTAL 1						1,199	2,383	904	3,287

STONE RIPRAP SCHEDULE (2 OF 4)											
LOCATION				LENGTH	WIDTH	STONE RIPRAP, CLASS A4	STONE RIPRAP, CLASS A5	STONE RIPRAP, CLASS B3	STONE RIPRAP, CLASS B4	STONE RIPRAP, CLASS B5	FILTER FABRIC
FROM STA.	OFFSET	TO STA.	OFFSET	FT	FT	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD
US ROUTE 34											
668+80	LT	670+97	LT	216	10			240			
669+42	RT	669+62	RT	24	20			53			
672+62	RT	672+82	RT	56	20			124			
674+93	RT	675+08	RT	56	15			93			
675+72	LT	676+22	LT	40	30			133			
677+80	RT	679+50	RT	170	10				189		189
678+70	LT	680+56	LT	190	37		781				781
679+49	RT	680+25	RT	75	39	325					325
680+25	RT	681+50	RT	130	10				144		144
680+56	LT	681+75	LT	120	10				133		133
682+25	LT	682+45	LT	29	20			64			
687+73	RT	687+93	RT	29	20			64			
690+30	RT	692+00	RT	170	10			189			
692+00	RT	692+62	RT	65	10			72			
692+60	LT	692+80	LT	25	20				56		56
692+62	RT	692+82	RT	20	20				44		44
694+55	LT	694+73	LT	40	19				84		84
694+80	RT	695+00	RT	20	20				44		44
700+74	LT	700+92	LT	24	18					48	48
700+74	RT	701+11	RT	37	15			62			
720+12	LT	720+35	LT	22	22				54		54
720+12	RT	720+41	RT	33	32				117		117
739+70	RT	740+00	RT	30	16				53		53
740+00	RT	742+00	RT	200	16				356		356
742+00	RT	744+00	RT	200	20				444		444
742+00	RT BENCH	748+20	RT BENCH	620	14			964			
743+75	LT	745+00	LT	125	22				306		306
744+00	RT	745+20	RT	150	30		500				500
745+00	LT	746+50	LT	150	19				317		317
746+50	LT	748+50	LT	200	16				356		356
744+95	RT	745+05	RT	45	10					50	
747+00	RT DRIVE	747+40	RT DRIVE	45	20				100		100
747+40	RT DRIVE	748+50	RT DRIVE	150	14				233		233
749+28	RT	751+20	RT	210	13				303		303
749+61	LT	749+89	LT	28	24				75		75
749+89	LT	752+00	LT	210	22				513		513
750+00	LT DRIVE	751+10	LT DRIVE	110	9				110		110
751+20	RT	752+00	RT	80	18			160			
750+95	LT	751+05	LT	30	11				37		37
752+00	LT	754+10	LT	210	22				513		513
752+00	RT	752+20	RT	20	22				49		
754+10	LT	754+30	LT	20	20				44		44
754+30	LT	756+25	LT	195	19				412		412
755+30	RT	756+98	RT	170	13				246		246
757+27	LT	758+82	LT	80	100				889		889
SUBTOTAL 2						325	1,281	2,220	6,221	98	7,826

FILE NAME =	USER NAME = danw	DESIGNED - DBS	REVISED -
D468409-SHT-29-30-STONE RIP RAP.dgn		DRAWN - PSBA	REVISED -
	PLOT SCALE = 100.0000' / 1" =	CHECKED - CSB	REVISED -
	PLOT DATE = 11/16/2012	DATE - 10/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCALE: N.A.		SHEET NO. 29 OF 51 SHEETS		STA. TO STA.		F.A.P. RTE.		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
						313	7-2 ; 6-1	HENDERSON	976	58	
						CONTRACT NO. 68409		ILLINOIS FED. AID PROJECT			