

STONE RIPRAP SCHEDULE (3 OF 4)									
LOCATION				LENGTH	WIDTH	STONE RIPRAP, CLASS B3	STONE RIPRAP, CLASS B4	STONE RIPRAP, CLASS B5	FILTER FABRIC
FROM STA.	OFFSET	TO STA.	OFFSET	FT	FT	SO YD	SO YD	SO YD	SO YD
US ROUTE 34									
758+00	RT	759+00	RT	100	13			144	144
758+20	LT	759+00	LT	80	13			116	116
759+00	LT	760+00	LT	100	15			167	167
759+00	RT	759+75	RT	75	15			125	125
759+15	LT	759+35	LT	20	20			44	44
760+00	LT	761+00	LT	100	17			189	189
761+00	LT	762+00	LT	100	18			200	200
777+91	LT	778+10	LT	20	20		44		44
778+10	LT	779+05	LT	100	10		111		111
779+05	LT	779+20	LT	28	20			62	62
779+17	RT	780+43	RT	130	10		144		144
779+29	LT	784+05	LT	520	12		693		693
780+42	RT	780+62	RT	32	20		71		71
780+62	RT	781+42	RT	80	10		89		89
781+42	RT	781+70	RT	32	20		71		71
781+66	RT	784+20	RT	255	10		283		283
792+90	LT	793+10	LT	20	20		44		44
808+80	LT	809+85	LT	140	10		156		156
809+85	LT	810+14	LT	30	24		80		80
809+86	RT	810+06	RT	20	20		44		44
810+42	LT	811+70	LT	130	10		144		144
813+90	LT	814+10	LT	20	20	44			
821+19	LT	821+38	LT	20	20	44			
IL ROUTE 94 / 116									
14+76	LT	14+90	LT	24	20			53	53
15+00	RT	15+20	RT	20	20		44		44
18+40	LT	18+60	LT	20	20		44		44
41+06	RT	41+54	RT	45	15		75		75
41+36	LT	41+56	LT	20	20		44		44
42+26	LT	42+46	LT	20	20		44		44
42+26	RT	42+46	RT	20	20		44		44
45+58	RT	45+82	RT	24	12		32		32
RAMP A									
10+77	RT	11+12	RT	33	17		62		62
RAMP B									
8+84	LT	9+21	LT	30	25		83		83
8+89	RT	9+20	RT	45	15		75		75
RAMP C									
13+40	LT	13+60	LT	20	20		44		44
13+40	RT	13+40	RT	20	20		44		44
13+41	LT	13+51	LT	110	10		122		122
SUBTOTAL 3						89	2,736	1,100	3,836

STONE RIPRAP SCHEDULE (4 OF 4)											
LOCATION				LENGTH	WIDTH	STONE RIPRAP, CLASS A4	STONE RIPRAP, CLASS A5	STONE RIPRAP, CLASS B3	STONE RIPRAP, CLASS B4	STONE RIPRAP, CLASS B5	FILTER FABRIC
FROM STA.	OFFSET	TO STA.	OFFSET	FT	FT	SO YD	SO YD	SO YD	SO YD	SO YD	SO YD
BOGUS HOLLOW ROAD (1350 E)											
5+46	RT	6+08	RT	24	20					53	53
6+08	RT	7+19	RT	100	18					200	200
TR 111 (1350 E)											
151+55	RT	151+71	RT	16	10			18			
TR 94 (1400 E)											
44+74	LT	44+94	LT	20	20				44		44
53+99	LT	54+09	LT	20	10			22			
TR 138 (1650 E)											
44+97	LT	45+67	LT	60	10				67		67
46+31	LT	46+51	LT	20	20				44		44
53+28	LT	53+49	LT	22	18			44			
53+29	RT	53+49	RT	22	20				49		49
53+49	LT	54+00	LT	55	12			73			
TR 150 (1700 E)											
43+38	RT	43+72	RT	28	32					100	100
43+46	LT	43+65	LT	20	20				44		44
44+26	LT	44+48	LT	20	22				49		49
66+00	LT	66+35	LT	35	20				78		78
66+38	RT	66+67	RT	30	22				73		73
69+61	RT	70+61	RT	100	8			89			
TR 178 (1800 E)											
52+00	RT	53+15	RT	100	12				133		133
53+08	RT	53+26	RT	16	13				23		23
53+10	RT	53+25	RT	75	13				108		108
53+43	LT	53+52	LT	60	10				67		67
TR 190 (1850 E)											
51+27	RT	52+50	RT	125	9			125			
52+50	RT	54+75	RT	225	9			225			
DETOUR 1											
2550+98	LT	2551+29	LT	32	30					107	107
2551+30	RT	2553+25	RT	200	15				333		333
2553+97	RT	2554+07	RT	10	10			11			
DETOUR 3											
125+96	LT	126+22	LT	20	20				44		
126+09	LT	126+52	LT	50	8				44		
SUBTOTAL 4								696	1,114	460	1,573
SUBTOTAL 3								89	2,736	1,100	3,836
SUBTOTAL 2						325	1,281	2,220	6,221	98	7,826
SUBTOTAL 1								1,199	2,383	904	3,287
TOTAL						325	1,281	4,205	12,454	2,562	16,522

GROUT FOR USE WITH RIPRAP						
LOCATION				LENGTH	WIDTH	GROUT FOR USE WITH RIPRAP
FROM STA.	OFFSET	TO STA.	OFFSET	FT	FT	CU YD
US ROUTE 34						
739+70	RT	740+00	RT	30	16	11.7
740+00	RT	742+00	RT	200	16	78.3
742+00	RT	742+60	RT	60	20	29.3
747+40	RT	748+50	RT	150	14	51.3
749+28	RT	751+00	RT	190	13	60.3
751+00	RT	751+20	RT	20	13	6.4
758+00	RT	759+00	RT	100	13	31.7
759+00	RT	759+75	RT	75	15	27.5
BOGUS HOLLOW ROAD (1350 E)						
5+46	RT	6+08	RT	24	20	11.7
6+08	RT	7+19	RT	100	18	44.0
TOTAL						352.2

* APPLICATION RATE OF 0.22 CU YD / SO YD

FILE NAME = D468409-SHT-29-30-STONE RIP RAP.dgn	USER NAME = danw	DESIGNED - DBS	REVISED -
		DRAWN - PSBA	REVISED -
	PLOT SCALE = 100.0000' / 1" =	CHECKED - CSB	REVISED -
	PLOT DATE = 11/16/2012	DATE - 10/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
US ROUTE 34

SCALE: N.A. SHEET NO. 30 OF 51 SHEETS STA. TO STA.

F.A.P. RTE. 313	SECTION 7-2 ; 6-1	COUNTY HENDERSON	TOTAL SHEETS 976	SHEET NO. 59
CONTRACT NO. 68409				
ILLINOIS FED. AID PROJECT				