

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)		
LOCATION	WIDTH	AREA
	FT	SQ YD
SN 036-0062 (EB) - US 34		
STA 754+46.19 TO STA 755+48.30, RT	24.00	266.67
STA 759+14.07 TO STA 760+16.39, RT	24.00	266.67
SN 036-0063 (WB) - US 34		
STA 754+40.76 TO STA 755+42.87, LT	24.00	266.67
STA 759+08.64 TO STA 760+10.33, LT	24.00	266.67
SN 036-0065 - IL 94/116		
STA 24+32.64 TO STA 25+32.64	46.00	511.11
STA 28+03.64 TO STA 29+03.64	46.00	511.11
TOTAL		2,088.90
USE		2,089

SHOULDER RUMBLE STRIPS, 8 INCH	
LOCATION	FOOT
US ROUTE 34	88,998
IL 94/116	3,462
RAMP A	2,760
RAMP B	2,669
RAMP C	2,797
RAMP D	2,669
TOTAL	103,354

TEMPORARY RAMP SCHEDULE			
LOCATION	LENGTH	WIDTH	SQ YD
	FEET	FEET	
US ROUTE 34			
STA 515+25.00 TO STA 515+30.00	5.00	24.00	13.33
STA 824+70.00 TO STA 824+75.00	5.00	24.00	13.33
IL ROUTE 94 / 116			
STA 10+25.00 TO STA 10+30.00	5.00	26.00	14.44
STA 42+84.69 TO STA 43+14.69	5.00	26.00	14.44
BOGUS HOLLOW ROAD			
STA 9+43.22 TO STA 9+48.22	5.00	130.00	55.56
TR 94			
STA 51+29.37 TO STA 51+34.37	5.00	24.00	13.33
STA 42+84.69 TO STA 43+14.69	5.00	154.00	85.56
TR 150			
STA 51+36.52 TO STA 51+41.52	5.00	24.00	13.33
STA 70+97.50 TO STA 71+02.50	5.00	128.00	71.11
TR 178			
STA 51+36.52 TO STA 51+41.52	5.00	24.00	13.33
STA 55+70.62 TO STA 55+75.62	5.00	131.50	73.06
DETOUR No. 1			
STA 2553+05.00 TO STA 2553+10.00	5.00	24.00	13.33
DETOUR No. 2			
STA 1779+95.00 TO STA 1780+00.00	5.00	24.00	13.33
TOTAL			407.48
USE			408

AGGREGATE (PRIME COAT)				
LOCATION		SO YD	TON (0.002 TON/SQ YD)	NOTES
US ROUTE 34				
515+00.00	523+00.00	19200	38	US 34 ELT EASTBOUND LANE TIE-IN
813+00.00	824+13.00	26147	105	TEMPORARY RAMP (2 LIFTS)
DETOUR 1 - ROUTE US 34				
2547+90.00	2552+70.00	11532	23	DETOUR 1 @ EXISTING US ROUTE 34 TIE-IN
DETOUR 2 - ROUTE US 34				
1750+00.00	1784+67.00	11194	22	DETOUR 2 @ EXISTING US ROUTE 34 TIE-IN
TR-150 (1700E)				
59+00.00	71+02.00	32153	64	
TOTAL			253	

FILE NAME = D468409-SHT-31-33-PAVING.dgn	USER NAME = danw	DESIGNED - DBS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES US ROUTE 34		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / 1"	CHECKED - CSB	REVISED -				313	7-2 ; 6-1	HENDERSON	976	62
	PLOT DATE = 11/16/2012	DATE - 10/2012	REVISED -				CONTRACT NO. 68409				
SCALE: N.A.		SHEET NO. 33 OF 51 SHEETS		STA. TO STA.		ILLINOIS FED. AID PROJECT					