

SIGNING SCHEDULE (5 OF 8)					
			SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	WOOD SIGN SUPPORT
LOCATION	SIGN CODE	MESSAGE OR DESCRIPTION	SO. FT.	SO. FT.	FOOT
STATION	LT / RT				
BHR					
9+29	RT	W3-1 (30X30)	STOP AHEAD (PLACED 500 FT BEFORE)	6.25	17
	RT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
		R6-1R (36X12)	ONE WAY	3.00	
		R6-1L (36X12)	ONE WAY	3.00	
TR 111					
148+81	LT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
		R6-1R (36X12)	ONE WAY	3.00	
		R6-1L (36X12)	ONE WAY	3.00	
153+40	LT	W3-1 (30X30)	STOP AHEAD	6.25	17
TR 94					
39+10	RT	W13-1P (24X24)	ADVISORY SPEED PLAQUE	4.00	17
		W1-4 (36X36)	REVERSE CURVE	9.00	
44+36	RT	W3-1 (30X30)	STOP AHEAD	6.25	17
49+14	RT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
49+38	RT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
		R6-1R (36X12)	ONE WAY	3.00	
		R6-1L (36X12)	ONE WAY	3.00	
50+62	LT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
		R6-1R (36X12)	ONE WAY	3.00	
		R6-1L (36X12)	ONE WAY	3.00	
50+84	LT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
52+18	RT	W3-1 (30X30)	STOP AHEAD	6.25	17
52+64	LT	W3-1 (30X30)	STOP AHEAD	6.25	17
53+98	RT	R1-1 (36X36)	STOP	9.00	16
TR 102 NORTH					
		W14-1 (30X30)	DEAD END	6.25	16
		W8-1108 (30X30)	ROAD ENDS 500 FT	6.25	16
		OM4-1 (18X18)	OBJECT MARKER	2.25	12
		R11-1100 (48X30)	ROAD ENDS		10.00 28
		OM4-1 (18X18)	OBJECT MARKER	2.25	12
SUBTOTAL 5			178.25	10.00	322.00

SIGNING SCHEDULE (6 OF 8)					
			SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	WOOD SIGN SUPPORT
LOCATION	SIGN CODE	MESSAGE OR DESCRIPTION	SO. FT.	SO. FT.	FOOT
STATION	LT / RT				
TR 102 SOUTH					
		W14-1 (30X30)	DEAD END	6.25	16
		W8-1108 (30X30)	ROAD ENDS 500 FT	6.25	16
		OM4-1 (18X18)	OBJECT MARKER	2.25	12
		R11-1100 (48X30)	ROAD ENDS		10.00 28
		OM4-1 (18X18)	OBJECT MARKER	2.25	12
TR 119					
49+75	RT	R1-1 (36X36)	STOP	9.00	16
50+24	LT	R1-1 (36X36)	STOP	9.00	16
TR 122 NORTH					
		W14-1 (30X30)	DEAD END	6.25	16
		W8-1108 (30X30)	ROAD ENDS 500 FT	6.25	16
		OM4-1 (18X18)	OBJECT MARKER	2.25	12
		R11-1100 (48X30)	ROAD ENDS		10.00 28
		OM4-1 (18X18)	OBJECT MARKER	2.25	12
TR 122 SOUTH					
		W14-1 (30X30)	DEAD END	6.25	16
		W8-1108 (30X30)	ROAD ENDS 500 FT	6.25	16
		OM4-1 (18X18)	OBJECT MARKER	2.25	12
		R11-1100 (48X30)	ROAD ENDS		10.00 28
		OM4-1 (18X18)	OBJECT MARKER	2.25	12
TR 138					
44+16	RT	W3-1 (30X30)	STOP AHEAD	6.25	17
49+16	RT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
		R6-1R (36X12)	ONE WAY	3.00	
		R6-1L (36X12)	ONE WAY	3.00	
50+84	LT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
		R6-1R (36X12)	ONE WAY	3.00	
		R6-1L (36X12)	ONE WAY	3.00	
55+84	LT	W3-1 (30X30)	STOP AHEAD	6.25	17
TR 150					
40+68	RT	W13-1P (24X24)	ADVISORY SPEED PLAQUE	4.00	17
		W1-4 (36X36)	REVERSE CURVE	9.00	
44+22	RT	W3-1 (30X30)	STOP AHEAD	6.25	17
49+22	RT	R6-3 (30X24)	DIVIDED HIGHWAY	5.00	20
		R1-1 (36X36)	STOP	9.00	
		R6-1R (36X12)	ONE WAY	3.00	
		R6-1L (36X12)	ONE WAY	3.00	
SUBTOTAL 6			160.75	30.00	412.00

FILE NAME = D468409-SHT-40-43-SIGNING.dgn

USER NAME = danw

DESIGNED - DBS

REVISED -

DRAWN - PSBA

REVISED -

PLOT SCALE = 100.0000' / 1" =

CHECKED - CSB

REVISED -

PLOT DATE = 11/16/2012

DATE - 10/2012

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
US ROUTE 34**

SCALE: N.A.

SHEET NO. 42 OF 51 SHEETS

STA.

TO STA.

F.A.P. RTE. 313

SECTION 7-2 ; 6-1

COUNTY HENDERSON

TOTAL SHEETS 976 SHEET NO. 71

CONTRACT NO. 68409

ILLINOIS FED. AID PROJECT