ROBERT L. & SHARON SCOTT

NW 1/4 SEC 21
T-10-N, R-4-W

ROBERT L. & SHARON SCOTT

735+00.00
160.00' LT

PR ROW & A/C

CONST LIMIT

MATCH LINE STA. 728+00

MATCH LINE STA. 740+00

38500LT12

PR US 34 WB

38700LT12

730+00

Ⓔ US ROUTE 34

735+00

38450CL

38550CL

38650CL

38750CL

PR US 34 EB

38600RT12

10'
24'
4'
2'
60'
2'
4'
24'
10'

+25

+00

CONST LIMIT

PR ROW & A/C

730+00.00
130.00' RT

735+00.00
145.00' RT

739+00.00
145.00' RT

ROBERT L. & SHARON SCOTT

ROBERT L. & SHARON SCOTT

RESTRICTED USE SOILS

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL LIMITS SHOWN ARE ESTIMATED. EXACT LIMITS TO BE DETERMINED BY THE ENGINEER.

N

50' 0 50' 100'
HORIZONTAL SCALE

PLAN
DATE
BY
SURVEYED
PLOTTED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
CADD FILE NAME
NOTE BOOK
NO.

PROFILE
DATE
BY
SURVEYED
PLOTTED
CROSSES CHECKED
BM. NOTED
STRUCTURE NOTATNS CHKD
NOTE BOOK
NO.

ex = -0.81'
1,000.00' V.C.

VPI STA 730+53.01
VPI EL 684.19

VPT STA 735+53.01
VPT EL 677.14

-0.76%

-1.41%

EXISTING @ PROFILE

PROPOSED US ROUTE 34 AT P.G.L.

-1.41%

50'
5'

	700	695	690	685	680	675	670	665	660
EX @ EL / PR PGL EL	687.24 / 685.92	688.33 / 685.45	688.45 / 684.96	688.63 / 684.46	689.18 / 683.94	688.84 / 683.41	688.72 / 682.86	689.00 / 682.30	689.35 / 681.71
	728+00		729+00		730+00		731+00		732+00

EX @ EL / PR PGL EL	689.57 / 681.12	689.25 / 680.50	688.87 / 679.87	689.20 / 679.22	689.45 / 678.56	688.42 / 677.88	687.96 / 677.18	688.47 / 676.48	688.21 / 675.77	687.77 / 675.07	687.76 / 674.36	687.61 / 673.66	687.21 / 672.95	685.02 / 672.25	682.73 / 671.54	679.45 / 670.84									
	733+00		734+00		735+00		736+00		737+00		738+00		739+00		740+00										

FILE NAME = D:\68409-sht-20-plnprf-US34-19.dgn	USER NAME = zach1	DESIGNED - DBS	REVISED -	
		DRAWN - PSBA	REVISED -	
	PLOT SCALE = 100.0000 ' / in.	CHECKED - CSB	REVISED -	
	PLOT DATE = 10/16/2012	DATE - 10/2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROADWAY PLAN AND PROFILE
US ROUTE 34

SCALE: 1"=50' | SHEET NO. 20 OF 67 SHEETS | STA. 728+00 TO STA. 740+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	7-2 ; 6-1	HENDERSON	976	154
		CONTRACT NO. 68409		
	ILLINOIS FED. AID PROJECT			