## INDEX OF SHEETS

- I COVER SHEET
- 2 INDEX, STANDARDS AND GENERAL NOTES
- 3-4 SUMMARY OF QUANTITIES
- 5 TYPICAL SECTIONS
- 6-7 SCHEDULE OF QUANTITIES
- 8-12 PLAN AND PROFILE SHEETS 13 PARAPET RAILING DETAIL
- 14 CONCRETE BARRIER WALL DETAIL
- 15-22 CROSS SECTION SHEETS

## STANDARDS IN THE PLANS

	·
000001-06	STANDARD SYMBOLS. ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	
	PAVEMENT FABRIC
	PCC SHOULDER
542301-03	PRECAST REINFORCED CONCRETE FLARED END SECTION
542601-0 <b>3</b>	REINFORCED CONCRETE PIPE ELBOW
542606-0 <b>2</b>	REINFORCED CONCRETE PIPE TEE
602601-02	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
604001-03	FRAME AND LIDS, TYPE 1
630001 - <b>10</b>	STEEL PLATE BEAM GUARDRAIL
630301-06	SHOULDER WIDENING FOR TYPE I (SPECIAL) GUARDRAIL TERMINALS
631031-[[	TRAFFIC BARRIER TERMINAL, TYPE 6
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
	REFLECTOR MARKER AND MOUNTING DETAILS
637006- <b>03</b>	CONCRETE BARRIER 42 INCH (1065 mm) HEIGHT
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 4.5M (15') AWAY
701006-04	OFF-ROAD OPERATIONS, 2L, 2W, 4.5M (15') TO 600mm (24") FROM
	PAVEMENT EDGE.
701011-03	OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701201-04	LANE CLOSURE, 2L. 2W. DAY ONLY. FOR SPEEDS > 45 MPH
701306-03	LANE CLOSURE, 2L. 2W, SLOW MOVING OPERATIONS, DAY ONLY,
	FOR SPEEDS > 45 MPH
701901~ <b>0</b> 3	TRAFFIC CONTROL DEVICES

## GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION". ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET. AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK IN SECTION (L.K)1-2 INCLUDES FURNISHED EXCAVATION, PCC SIDEWALK, 6", PCC SIDEWALK, SPECIAL, CONSTRUCTION OF PCC SHOULDERS, CONCRETE BARRIER, DOUBLE FACE, 42", PIPE DRAINS, CONCRETE PIPE CULVERTS, ADJUSTING CATCH BASINS SHAPING AND REGRADING DITCHES AGGREGATE SHOULDERS, ERECTION OF STEEL PLATE BEAM GUARDRAIL, INSTALLATION OF IMPACT ATTENUATORS, AND ALL OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

THE PROPOSED PROJECT BEGINS AT THE INTERSECTION OF OUTER BELT WEST AND CONTINUES EAST TO SCHWERMAN AVE. ALONG U.S. 40 IN EFFINGHAM.

ALL ELEVATIONS SHOWN IN PLANS ARE BASED ON U.S.G.S. DATUM.

ALL DISTURBED AREAS WITHIN THE CONSTRUCTION LIMITS SHALL BE FERTILIZED AND SEEDED. SEEDING SHALL BE CLASS 2 IN ACCORDANCE WITH THE SPECIAL PROVISIONS AND THE APPLICABLE ARTICLES OF SECTION 250 OF THE STANDARD SPECIFICATIONS.

THE MATERIAL USED FOR AGGREGATE SHOULDERS. TYP B SHALL BE EITHER CRUSHED STONE OR CRUSHED CONCRETE.

THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS AND MUST BE CONSIDERED APPROXIMATE. FIELD MARKINGS OF ACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

COUNTY TOTAL SHEE SHEETS NO.

EFFINGHAM 22 2 CONTRACT NO. 74316

SECTION (L,K)I-2

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED TO CALCULATE PLAN QUANTITIES:

GRANULAR MATERIAL

2.05 TON/CU.YD.

FILE NAME :	USER NAME < atofformk	DESIGNED -	REVISED -		INDEX OF SHEETS AND		
o:\p+_work\p+idat\stoffenmk\dms58671\d7	74316-shs-rindexidgn	DRAWN -	REVISED -	STATE OF ILLINOIS	f		
	PLOY SCALE * 40.0000 1/ 10:	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	GENERAL NOTES		
	PLOT 041E = 10/2/2012	DATE -	REVISED -		SCALE: NA	SHEET NO. 1 OF 1 SHEETS STA.	TO STA.