

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	INDEX OF SHEETS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	LOCATION DESCRIPTIONS
5-27	EXISTING STRUCTURE PLANS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 27:

STANDARD 701101-03	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701106-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701400-06	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701402-09	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701406-06	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701411-08	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701423-06	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701901-03	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2012; THE SUPPLEMENTAL SPECIFICATIONS, THE RECURRING SPECIAL PROVISIONS, AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THE PROPOSED PROJECT IS LOCATED AT 3 LOCATIONS IN MACON COUNTY IN DISTRICT 7. LOCATION 1 IS AT STRUCTURE NUMBERS 058-0101 AND 058-0102 ON NORTHBOUND AND SOUTHBOUND US ROUTE 51 IN MACON COUNTY. LOCATION 2 IS AT STRUCTURE NUMBERS 058-0108 AND 058-0109 ON NORTHBOUND AND SOUTHBOUND US ROUTE 51 IN MACON COUNTY. LOCATION 3 IS AT STRUCTURE NUMBERS 058-0093 AND 058-0094 ON EASTBOUND AND WESTBOUND INTERSTATE 72 IN MACON COUNTY.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF CLEANING AND PAINTING THE BRIDGES AS SPECIFIED IN THE PLANS AND SPECIAL PROVISIONS.

THE STRUCTURAL STEEL SHALL BE CLEANED AND PAINTED AS SPECIFIED IN THE PLANS AND THE SPECIAL PROVISIONS.

ALL DECK DRAINS SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - OZ/E/U. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED AT THEIR OWN EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ONLY STRUCTURAL STEEL IS TO BE PAINTED. ALL OTHER SURFACES WILL BE PROTECTED FROM BEING PAINTED. ALL PAINT AND OVERSPRAY WILL BE REMOVED AT THE CONTRACTOR'S EXPENSE.

THE SSPC OP1 AND OP2 PAINTING CONTRACTOR CERTIFICATION WILL BE REQUIRED FOR THIS PROJECT.

\* VARIOUS ROUTES  
\*\* 07 BRIDGE PAINTING 2013-2

FILE NAME *	USER NAME * stafffrank	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS AND GENERAL NOTES</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\spw\dot\stafffrank\0307267\074580-ahc-index.dgn	DRAWN -	REVISED -						*	**	MACON	27	2
PLOT SCALE * 100.0000 / 1 in.	CHECKED -	REVISED -			CONTRACT NO. 74580			[ILLINOIS] FED. AID PROJECT				
Default	DATE -	REVISED -			SCALE: N/A	SHEET 1	OF 1	SHEETS	STA.	TO STA.		