CODE NUMBER	PAY ITEM	CONSTRUCTION TYPE CODE 0011	
		UNIT	035-0016 FUNDING 80% FEDERAL, 20% STATE
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	135
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	79
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	139
44000100	PAVEMENT REMOVAL	SQ YD	199
44004250	PAVED SHOULDER REMOVAL	SQ YD	546
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	553
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	329
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	49.2
50300225	CONCRETE STRUCTURES	CU YD	74.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	267.9
50300260	BRIDGE DECK GROOVING	SQ YD	650
50300280	CONCRETE ENCASEMENT	CU YD	4.8
50300300	PROTECTIVE COAT	SQ YD	745

FILE NAME : c:\pw_work\pwidot\kellegh\d0242339\78152-shtercvr_sqq_index.dgn

USER NAME = $USER$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN -	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 10/17/2012	DATE -	REVISED -	

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	11B-1	HARDIN	50	4

CONTRACT NO. 78152

ILLINOIS FED. AID PROJECT