

CODE NUMBER	PAY ITEM	CONSTRUCTION TYPE CODE 0011	
		UNIT	035-0016 FUNDING 80% FEDERAL, 20% STATE
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	1877
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	626
70400100	TEMPORARY CONCRETE BARRIER	FOOT	287.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	275
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
* 70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1
* 70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	2836
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	5
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	4

\* SPECIALTY  
ITEM

FILE NAME : c:\pwworkspace\11111111\11111111.dgn

USER NAME : USER*	DESIGNED -	REVISED -
PLOT SCALE : 100.0000 / 1"	DRAWN -	REVISED -
PLOT DATE : 10/17/2012	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 885	SECTION 11B-1	COUNTY HARDIN	TOTAL SHEETS 50	SHEET NO. 7
CONTRACT NO. 78152				ILLINOIS FED. AID PROJECT