

REMOVAL SCHEDULE

LOCATION STATION	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	GUARDRAIL REMOVAL	REMOVING INLETS
IL 146 (FAP 885)	SO YD	SO YD	FOOT	EACH
NW QUAD				
STA. 226+43.00 TO STA. 227+77.00		102		
STA. 227+20.00 TO STA. 227+99.00			80	
STA. 227+30.00 TO STA. 227+67.00	57			
STA. 229+75.00				1
NE QUAD				
STA. 228+76.00 TO STA. 231+03.00			230	
STA. 228+87.00 TO STA. 229+25.00	44			
STA. 228+93.00 TO STA. 231+63.50		123		
SW QUAD				
STA. 224+95.00 TO STA. 227+61.00		166		
STA. 226+00.00 TO STA. 227+80.00			179	
STA. 227+30.00 TO STA. 227+67.00	41			
SE QUAD				
STA. 228+57.00 TO STA. 229+36.00			79	
STA. 228+80.00 TO STA. 230+61.00		155		
STA. 228+87.00 TO STA. 229+25.00	57			
TOTALS	199	546	568	1

SHOULDER SCHEDULE

LOCATION STATION	HMA SHOULDERS, 8"	HMA BASE COURSE WIDENING, 10"	HMA SHOULDERS, 10"
IL 146 (FAP 885)	SO YD	SO YD	SO YD
NW QUAD			
STA. 226+43.00 TO STA. 227+87.00	116		
STA. 226+43.00 TO STA. 227+75.00		61	
NE QUAD			
STA. 228+89.00 TO STA. 231+63.50	304		
STA. 228+95.00 TO STA. 230+32.00		74	
SW QUAD			
STA. 224+95.00 TO STA. 226+14.00	133		
STA. 226+14.00 TO STA. 227+67.00			143
SE QUAD			
STA. 228+68.50 TO STA. 230+61.00			186
TOTALS	553	135	329

EARTHWORK SCHEDULE

LOCATION STATION	EARTH EXCAVATION	CHANNEL EXCAVATION	SHRINKAGE FACTOR FOR EARTH EXCAVATION	EARTH EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	FURNISHED EXCAVATION
IL 146 (FAP 885)	CU YD	CU YD	%	CU YD	CU YD	CU YD	CU YD
WEST							
STA. 224+95.00 TO STA. 228+35.00	42	36	25	31	94	-63	63
EAST							
STA. 228+18.00 TO STA. 231+63.50	52	40	25	39	516	-477	477
TOTALS	94	76		70	610	-540	540

FILE NAME = c:\pwworkspace\kell\proj\80242339\78152-ah1a.cvr...sqv_index.dgn

USER NAME = *USER*	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
PLOT DATE = 10/17/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	11B-1	HARDIN	50	10
CONTRACT NO. 78152				
ILLINOIS FED. AID PROJECT				