

GENERAL NOTES

- 1) THE THICKNESS OF HOT-MIX ASPHALT MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT MIXTURE IS PLACED.
- 2) FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES:

ALL HOT MIX ASPHALT	2.016 TONS/CU YD
BITUMINOUS MATERIALS: ON PAVEMENT	0.09 GAL /SQ YD
- 3) PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS THE RESIDENT ENGINEER SHOULD CONTACT THE BUREAU OF OPERATIONS AND ARRANGE FOR INSPECTION AND APPROVAL OF THE PAVEMENT MARKING LAYOUT.
- 4) IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 101.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
- 5) COMMITMENTS: NONE AS OF OCTOBER 19, 2012.

STANDARDS

- | | |
|-----------|---|
| 000001-06 | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS |
| 701001-02 | OFF-ROAD, 2L2W MORE THAN 15' FROM PAVEMENT EDGE |
| 701006-04 | OFF-ROAD, 2L2W 15' TO 24" FROM PAVEMENT EDGE |
| 701201-04 | LANE CLOSURE, 2L2W DAY ONLY, FOR SPEEDS \geq 45 MPH |
| 701901-03 | TRAFFIC CONTROL DEVICES |

MIXTURE REQUIREMENTS

LOCATION(S):	FAS 825 SURFACE
MIXTURE USE(S):	HOT-MIX ASPHALT SURFACE COURSE
AC/PG:	PG 64-22
RAP% (MAX):	10%
DESIGN AIR VOIDS:	4% @ Ndes 90
MIXTURE COMPOSITION: (GRADATION MIXTURE):	IL 9.5 mm OR IL 12.5 mm
FRICTION AGGREGATE:	MIXTURE C
MIXTURE WEIGHTS:	112LBS / SY / INCH THICKNESS

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS; GENERAL NOTES; STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4 GENERAL PLAN AND ELEVATION
- 5 BUTT JOINT DETAIL
- 6 CROSS SECTION

Prepared By: *Joe B. Anderson*
DISTRICT STUDIES & PLANS ENGINEER

Examined By: *Paul S. G.*
DISTRICT LAND ACQUISITION ENGINEER

Examined By: *Cami Nilsen*
DISTRICT PROGRAM DEVELOPMENT ENGINEER

Examined By: *Will M. G.*
DISTRICT OPERATIONS ENGINEER

Examined By: *[Signature]*
DISTRICT PROJECT IMPLEMENTATION ENGINEER

Examined By: *Doris A. [Signature]*
DISTRICT CONSTRUCTION ENGINEER

Examined By: *[Signature]*
DISTRICT MATERIALS ENGINEER

Approved By: *Ormer A. [Signature]*
DEPUTY DIRECTOR OF HIGHWAYS, REGION 5 ENGINEER

DATE: *Sept 26 2012*

••09 CM BRIDGE REPAIR 2013-1

FILE NAME =	USER NAME = walkera	DESIGNED - RAW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIGNATURES, GENERAL NOTES, STANDARDS, & INDEX OF SHEETS	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
01\pw_work\p1dot\walkera\0299139\sh-	plan.dgn	DRAWN - RAW	REVISED -			825	**	JEFFERSON	6	2	
	PLOT SCALE = 100.0000' / in.	CHECKED - TWH	REVISED -			CONTRACT NO. 78307					
	PLOT DATE = 9/17/2012	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET OF SHEETS		STA. TO STA.			