STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

100

0

0

0

FOR INDEX OF SHEETS, SEE SHEET NO. 2 FOR STATE STANDARDS, SEE SHEET NO. 2


PROPOSED HIGHWAY PLANS

FAI ROUTE 74 (I-74) SECTION: (37-2HB)BP

PROJECT: NHPP-QWEG(442)


TYPE of IMPROVEMENT: BRIDGE PAINTING

HENRY COUNTY




D.92-052-18





PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

HENRY COUNTY
COLONA TOWNSHIP — SECTIONS 25 & 36



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1-800-892-0123
OR 811

PROJECT ENGINEER: DAVID DOSS (815) 284–5416
PROJECT MANAGER: MAHMOUD ETEMADI (815) 284–5393

CONTRACT NO. 64N07

INDEX OF SHEETS

INDEX OF SHEETS / STATE STANDARDS / GENERAL NOTES SUMMARY OF QUANTITIES

SCHEDULE OF QUANTITIES

5 STAGING TYPICAL
6-9 TRAFFIC CONTROL PLAN - STAGE I FOR SN 037-0102
10-13 TRAFFIC CONTROL PLAN - STAGE II FOR SN 037-0102
14-17 TRAFFIC CONTROL PLAN - STAGE III FOR SN 037-0102
18-23 TRAFFIC CONTROL PLAN - STAGE IV FOR SN 037-0102

24-26 EXISTING PLAN SHEETS (FOR INFORMATION ONLY)

STATE STANDARDS

701101-05 OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5m) TO 24" (600mm) FROM PAVEMENT EDGE LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY 701301-04 701400-09 LANE CLOSURE, FREEWAY/EXPRESSWAY

LANE CLOSURE, FREEWAY/EXPRESSWAY WITH BARRIER

LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS

45 MPH

LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS

45 MPH

TRAFFIC CONTROL DEVICES 701401-12 701402-12 701411-09 701426-09 701901-08 TEMPORARY CONCRETE BARRIER
METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
TELESCOPING STEEL SIGN SUPPORT 704001-08 720011-01 APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS) 729001-01

GENERAL NOTES

A MINIMUM OF 2 AIR MONITORS WILL BE REQUIRED TO MONITOR ABRASIVE BLASTING OPERATIONS, SEE SPECIAL PROVISION FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES".

THE CONTRACTOR SHALL SEED ALL DISTURBED AREAS WITHIN THE PROJECT LIMITS. SEEDING CLASS 2A SHALL BE USED. THIS WORK WILL BE INCLUDED IN THE CONTRACT UNIT PRICE PER LUMP SUM FOR CLEANING AND PAINTING STEEL

FERTILIZER SHALL BE APPLIED TO ALL DISTURBED AREAS AND INCORPORATED INTO THE SEEDBED PRIOR TO SEEDING OR PLACEMENT OF SOD AT THE RATE SPECIFIED IN SECTIONS 250 AND 252 OF THE STANDARD SPECIFICATIONS. THIS WORK SHALL BE INCLUDED IN THE COST OF CLEANING AND PAINTING STEEL BRIDGE NO. 1.

MULCH METHOD II SHALL BE APPLIED OVER ALL SEEDED AREAS. THIS SHALL BE INCLUDED IN THE COST OF THE CLEANING AND PAINTING STEEL BRIDGE NO. 1.

ALL BORROW/WASTE/USE SITES MUST BE APPROVED BY THE DEPARTMENT PRIOR TO REMOVING ANY MATERIAL FROM THE PROJECT OR INITIATING ANY EARTHMOVING ACTIVITIES, INCLUDING TEMPORARY STOCKPILING OUTSIDE THE LIMITS OF

TEMPORARY IMPACT ATTENUATORS WILL BE MEASURED AS EACH FOR EACH ATTENUATOR SUPPLIED ON THE JOB AS SPECIFIED IN THE PLANS, AND SHALL INCLUDE THE COST OF RENTING/OWNING THE ATTENUATOR FOR THE TIME REQUIRED ON THE JOB PLUS HAULING TO AND FROM THE PROJECT SITE, AS WELL AS ONE PLACEMENT AND REMOVAL FROM THE ROADWAY. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR IMPACT ATTENUATORS, TEMPORARY OF THE TYPE SPECIFIED.

RELOCATE TEMPORARY IMPACT ATTENUATOR WILL BE PAID FOR AS EACH AND WILL BE PAID FOR EACH TIME THE ATTENUATOR IS REQUIRED BY STAGING TO BE PICKED UP AND MOVED TO A DIFFERENT LOCATION ON THE PROJECT, WHETHER IT IS TO ANOTHER LOCATION ON THE ROADWAY OR TO A STORAGE/STAGING LOCATION FOR THE PROJECT. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR IMPACT ATTENUATORS, RELOCATE OF THE TYPE SPECIFIED.

THIS WORK SHALL BE DONE IN ACCORDANCE WITH SECTION 704 OF THE STANDARD SPECIFICATIONS. TEMPORARY CONCRETE BARRIER WILL BE MEASURED IN FEET ALONG THE CENTERLINE OF THE BARRIER AND SHALL INCLUDE THE COST OF RENTING/OWNING THE BARRIER FOR THE TIME REQUIRED ON THE JOB PLUS HAULING TO AND FROM THE PROJECT SITE, AS WELL AS ONE PLACEMENT AND REMOVAL FROM THE ROADWAY IN ACCORDANCE WITH SECTION 704 OF THE STANDARD AND SPECIFICATION. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR TEMPORARY CONCRETE BARRIER.

RELOCATE TEMPORARY CONCRETE BARRIER WILL BE PAID FOR IN FEET ALONG THE CENTERLINE OF THE BARRIER, AND WILL BE PAID FOR EACH TIME THE BARRIER IS REQUIRED BY STAGING TO BE PICKED UP AND MOVED TO A DIFFERENT LOCATION ON THE PROJECT, WHETHER IT IS TO ANOTHER LOCATION ON THE ROADWAY OR TO A STORAGE/STAGING LOCATION FOR THE PROJECT. THIS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR RELOCATE TEMPORARY CONCRETE BARRIER.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123.

THE SSPC QP1 & QP2 CONTRACT CERTIFICATIONS WILL BE REQUIRED FOR THIS CONTRACT.

USER NAME = dossdd	DESIGNED	REVISED	
	DRAWN	REVISED	
PLOT SCALE = 40.0000 / in.	CHECKED	REVISED	
PLOT DATE = Oct-01-2018 02:45:31 PM	DATE	REVISED	

	INDEX OF SHEETS,					SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
STATE STANDARDS & GENERAL NOTES				74	(37-2HB)BP	HENRY	26	2	
	STATE STANDARDS & GENERAL NOTES						CONTRAC	T NO. 6	4N07
	SHEET	OF	SHEETS STA.	TO STA.	ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

0047 90% NHPP 10% STATE

			10% STATE	
CODE NUMBER	ITEM	UNIT	HENRY COUNTY	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1
70107004	PAVEMENT MARKING BLACKOUT TAPE, 4"	FOOT	1320	1320
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	440	440
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	9675	9675
70400100	TEMPORARY CONCRETE BARRIER	FOOT	462.5	462.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	712.5	712.5
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3
X5067501	BRIDGE CLEANING AND PAINTING WARRANTY NUMBER 1	L SUM	1	1
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	3225	3225
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1

USER NAME = dossdd	DESIGNED	-	 REVISED	-	
	DRAWN	-	 REVISED	-	
PLOT SCALE = 40.0000 ' / in.	CHECKED	-	 REVISED	-	
PLOT DATE = Oct-01-2018 02:45:40 PM	DATE	-	 REVISED	-	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

					F.A.I. RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
SUMMARY OF QUANTITIES					74	(37-2HB)BP		HENRY	26	3
								CONTRACT	NO. 64	1N07
EET	OF	SHEETS	STA	TO STA	i	Lucinois	L EED A	D DDOLECT		

SCHEDULE OF QUANTITIES

70400100	TEMPROARY CONCRETE E	BARRIER COMMENTS	FOOT	70300150	SHORT TERM LOCATION	PAVEMEN COMMI	T MARKING REMOVAL <u>ENTS</u>	<u>SQ FT</u>
	STAGE I	COMMENTS	1001		STAGE II			
	STA 785+50-788+75	TANGENT	325		660'	BLACK	OUT TAPE, 4"	220
	STA 788+75-789+87.5		112.5		STAGE III			
	STAGE II	77.11 2.1	11213		660'	BLACK	OUT TAPE, 4"	220
	STA 789+87.5-790+12.	5TAPER	25					
		TOTAL	462.5				TOTAL	440
		1017.12	10213	70300904	PAVEMENT MAR	VINC TADE	TVDE IV/ 4"	
				70300904	LOCATION		COMMENTS	<u>FOOT</u>
70400200	RELOCATE TEMPROARY C	ONCRETE BARRIER			STAGE I		COMMENTS	<u>1001</u>
70400200	LOCATION	COMMENTS	<u>FOOT</u>		STA 785+50-7	794±25	GTANGENT	875
	STAGE II	COMMENTS	1001		STA 794+25-8		TAPER	1000
	STA 788+75-790+12.5	TAPER	137.5		STAGE II	701123	7,11,211	1000
	STAGE III				STA 784+05-7	795±15	TAPER x2	280
	STA 783+87.5-785+25	TAPER	137.5		STA 785+45-7		TANGENT x2	760
	STA 785+25-788+50	TANGENT	325		STA 789+25-7		TAPER x2	280
	STAGE IV				STA 794+25-7		GTANGENT	140
	STA 784+12.5-785+25	TAPER	112.5		STA 795+65-8		TAPER	1000
		TOTAL	712.5		STAGE III			
		1017/12	, 12,3		STA 768+35-7	78+35	TAPER	1000
					STA 778+35-7		CTANGENT	500
					STA 783+35-7		TAPER x2	280
70107004	PAVEMENT MARKING BLA	CKOUT TAPE, 4"			STA 784+75-7		TANGENT ×2	760
	<u>LOCATION</u>	<u>COMMENTS</u>	<u>FOOT</u>		STA 788+55-7	789+95	TAPER x2	280
	STAGE I				STAGE IV			
	STAGE II	NONE REQUIRED			STA 759+75-7	⁷ 64+75	TAPER	500
		TAPER (LEFT SHOULDER)	140		STA 764+75-7	769+75	TANGENT	500
	STA 784+05-785+45	TANGENT (LEFT SHOULDER)	380		STA 769+75-7	79+75	TAPER	1000
	STA 785+45-789+25 STA 789+25-790+65	TAPER (LEFT SHOULDER)	140		STA 783+35-7	′88+55	QTANGENT	520
	STAGE III	THE CELL SHOOLSEN,	110				TOTAL	9675
		TAPER (RIGHT SHOULDER)	140					
	STA 783+35-784+75	TANGENT (RIGHT SHOULDER						
	STA 784+75-788+55 STA 788+55-789+95	TAPER (RIGHT SHOULDER)	140	X7030005	ΤΕΜΡΟΒΔΒΥ ΡΔ	VEMENT M	ARKING REMOVAL	
	STAGE IV	TATER (MOTT SHOOLDER)	140	X7030003	LOCATION	COMMEN.		SQ FT
	STAGE IV	NONE REQUIRED			STAGE I	COMMITTER	<u></u>	
		NONE REQUIRED			1875'	MARKING	TAPE, TYPE IV, 4"	625
		TOTAL	1320		STAGE II		,	
		TOTAL	1320		2460'	MARKING	TAPE, TYPE IV, 4"	820
					STAGE III			
					2820'	MARKING	TAPE, TYPE IV, 4"	940
					STAGE IV			
					2520'	MARKING	TAPE, TYPE IV, 4"	840
							TOTAL	3225

FILE NAME: DW:VIL

JSER NAME = dossdd

PLOT DATE = Oct-01-2018 02:45:54 PM

DESIGNED -

CHECKED

DRAWN

REVISED

REVISED -

REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES


SEET __ OF __ SHEETS STA. ____ TO STA.


 F.A.I. RTE.
 SECTION
 COUNTY SHEETS
 TOTAL SHEETS
 SHEET NO.

 74
 (37-2HB)BP
 HENRY
 26
 4

 CONTRACT NO. 64N07

STAGING TYPICAL





MODEL: Default

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION


REVISED


 STAGING TYPICAL
 RTE.
 SECTION
 COUNTY SHEETS NO.


 74
 (37-2HB)BP
 HENRY
 26
 5


 CONTRACT NO. 64N07


 SHEET
 OF
 SHEETS
 STA.
 ILLINOIS FED. AID PROJECT

















































CONTRACT NO. 64N07

