

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

*Various Routes  
OVD SIN STR REP & REPL 2007-9  
Various Counties  
Sheet 14 of 50  
Contract Number 44933*

*District 2  
Schedule of Locations for Overhead Sign Structure Replacement*

Location No.:	2-01	State I.D. No.:	2C101ABU0R000.0(174)				
County:	Winnebago	Route:	Auburn	M.P.:	0	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	93.00					
REMOVE & REINSTALL WALKWAY	FOOT	15.50					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
OVERHEAD SIGN STRUCTURE CANTILEVER TYPE II-C-A	FOOT	30.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
REBUILD CONCRETE FOUNDATATION FOR OVERHEAD SIGN ST	EACH	1.00					
This sign structure is being completely replaced.							

Location No.:	2-04	State I.D. No.:	2S101U020L018.5				
County:	Winnebago	Route:	US 20	M.P.:	18.5	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	73.50					
DRILL SHAFT CONCRETE FOUNDATION	CU YD	20.40					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	2.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					

Location No.:	2-02	State I.D. No.:	2S101S251R004.6				
County:	Winnebago	Route:	IL 251	M.P.:	4.6	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	73.50					
DRILL SHAFT CONCRETE FOUNDATION	CU YD	20.40					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	2.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					

Location No.:	2-03	State I.D. No.:	2S101U020L019.0				
County:	Winnebago	Route:	US 20	M.P.:	19	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	73.50					
DRILL SHAFT CONCRETE FOUNDATION	CU YD	20.40					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	2.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					