

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN 1 WITH INSTALLED PANEL 2 ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 2.3 SQ. M. (25.70 SQ. FT.)

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)
UNLESS OTHERWISE SHOWN. ILLINOIS DEPARTMENT OF TRANSPORTATION TEMPORARY INFORMATION SIGNING SCALE: DRAWN BY DESIGN DATE: 4/3/2006 CHECKED BY TC22

REVISION DATE: 02/02/99

tista/tis22.dm 4/3/2006 6:28:16 AN User-anethani

| DATE = 4/3/2006 | NAME = widststalto22.dgn | SCALE = 50.000 / IN. | RAME = obsbowa