
BITUMINOUS SHOULDER



t = SEE TYPICAL SECTIONS
FOR THICKNESS

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

GENERAL NOTES

THE BITUMINOUS SHOULDER SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 482 EXCEPT THE TOP LIFT SHALL BE BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE C, N50. THE WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER TON FOR BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE C, N50, AND SQUARE YARD FOR BITUMINOUS SHOULDERS SUPERPAVE OF THE THICKNESS SPECIFIED.

USE BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE C, N50, WHEN RESURFACING EXISTING BITUMINOUS SHOULDERS. THE THICKNESS IS SHOWN ON THE TYPICAL SECTIONS. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER TON FOR BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE C, N50.

REMOVAL OF MATERIAL FOR PLACEMENT OF THE BITUMINOUS SHOULDER TO BE PAID FOR IN UNITS FOR EXCAVATING AND GRADING EXISTING SHOULDERS OR IN CUBIC YARDS FOR EARTH EXCAVATION OR EARTH EXCAVATION WIDENING.

* 4% WHEN MAINLINE IS ON TANGENT. FOR CROSS SLOPE ON SUPERELEVATION SECTION, SEE HIGHWAY STANDARD 482001 OR 482006.


BITUMINOUS SHOULDER

23.4a

REVISED 5-30-03

PAVEMENT PATCHING FOR BITUMINOUS SURFACED PAVEMENT

| CONTRACT NO. 64563 | F.A.U | SECTION | COUNTY | TOTAL SHEET | NO. 5564 | 111-M-1 | WHITESIDE | 78 | 38 | STA. | TO STA. | FED. ROAD DIST. NO. | ILLINOIS | FED. AID | PROJECT |



SEQUENCE OF CONSTRUCTION:

- 1. REMOVE THE EXISTING BITUMINOUS SURFACE.
- 2. RESIDENT ENGINEER WILL DETERMINE IF LOCATION IS TO BE PATCHED OR TO ONLY REPLACE BITUMINOUS SURFACE.
- 3. REMOVE AND REPLACE FULL DEPTH PATCHES AT LOCATIONS DIRECTED BY THE ENGINEER.
- 4. REPLACE BITUMINOUS SURFACE OVER FULL DEPTH PATCHES AND AT LOCATIONS OF BITUMINOUS SURFACE REMOVAL.

GENERAL NOTES:


- THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 300 (12) WIDER ON EACH SIDE OF THE TRENCH.
- FOR BASIS OF PAYMENT: SEE SPECIAL PROVISION "PATCHING WITH BITUMINOUS OVERLAY REMOVAL".

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

PAVEMENT PATCHING FOR BITUMINOUS SURFACED PAVEMENT

REVISED 6-21-0

TYPICAL BENCHING ON EXISTING EMBANKMENT



TREE REPLACEMENT SCHEDULE

12
10
10

GENERAL NOTES:

LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT

MULCH SHALL BE HARDWOOD CHIPS, 5' WIDTH, 4" THICK WITH WEED BARRIER FABRIC

ALTERNATE PLANTING SITE FAI-88 / US 30 INTERCHANGE

TYPICAL BENCHING ON EXISTING EMBANKMENT

50.4

TREE REPLACEMENT SCHEDULE

90.4

32.4