

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	12.3.4155	WINNEBAGO	46	3
STA.	TO STA.			
	FED. AID PROJECT			

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED 20% STATE 1000 TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	1253
20400800	FURNISHED EXCAVATION	CU YD	679
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	359
25000210	SEEDING, CLASS 2A	ACRE	0.45
25100115	MULCH, METHOD 2	ACRE	0.45
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	360
28000300	TEMPORARY DITCH CHECKS	EACH	6
28000500	INLET AND PIPE PROTECTION	EACH	2
31100910	SUBBASE GRANULAR MATERIAL, TYPE A, 12"	SQ YD	2845
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	149
40600300	AGGREGATE PRIME	TON	335
40600545	LEVELING BINDER (HAND METHOD), N90	TON	164
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	12257
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4779
40600990	TEMPORARY RAMP	SQ YD	792
40601005	HOT - MIX ASPHALT REPLACEMENT OVER PATCHES	TON	606
40603310	HOT - MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	15558
40603570	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE MIX "E" N90	TON	18687
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	58

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED 20% STATE 1000 TOTAL QUANTITY
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	2649
42001300	PROTECTIVE COAT	SQ YD	2649
44000100	PAVEMENT REMOVAL	SQ YD	152
44000158	HOT - MIX ASPHALT SURFACE REMOVAL - 2 1/4"	SQ YD	30308
44002214	HOT - MIX ASPHALT REMOVAL OVER PATCHES - 3 1/2 INCH	SQ YD	3089
44004250	PAVED SHOULDER REMOVAL	SQ YD	1071
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	644
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	141
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	187
44213100	PAVEMENT FABRIC	SQ YD	818
44213200	SAW CUTS	FOOT	9938
48101200	AGGREGATE SHOULDERS, TYPE B	TON	7589
50105220	PIPE CULVERT REMOVAL	FOOT	80
542D0217	PIPE CULVERT, CLASS D, TYPE 1, 12"	FOOT	104
542D0223	PIPE CULVERT, CLASS D, TYPE 1, 18"	FOOT	544
64200105	SHOULDER RUMBLE STRIP	FOOT	150718
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5
67100100	MOBILIZATION	L SUM	1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	2

PLOT DATE = Mon Dec 15 11:50:17 2008  
 FILE NAME = P:\CADD\US220\winnebago\1239\summary28.dgn  
 PLOT SCALE = 50.00000 / IN  
 USER NAME = mcklauba