

F.A.P. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	12.3.418S	WINNEBAGO	46	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED 20% STATE 1000 TOTAL QUANTITY
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	25
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20
70300100	SHORT TERM PAVEMENT MARKING	FOOT	32,842
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4299
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8 INCH	FOOT	12680
* 78000620	THERMOPLASTIC PAVEMENT MARKING - LINE 18 INCH	FOOT	72
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	19730
* 78008310	POLYUREA PAVEMENT MARKING, TYPE 2 - LINE 4 INCH	FOOT	159082
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2226

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED 20% STATE 1000 TOTAL QUANTITY
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	907
X0322288	MEDIAN CLOSURE	EACH	2
X0322392	BEVELED PIPE AND GUARD	EACH	2
X0322729	MATERIAL TRANSFER DEVICE	TON	30944
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0017100	DOWEL BARS	EACH	3968
Z0028415	GEO TECHNICAL REINFORCEMENT	SQ YD	3817
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	162
Z0065752	SLOTTED DRAIN, 12", WITH 6" SLOT	FOOT	276
Z0075300	TIE BARS	EACH	100

* Specialty Items

Plot Date: Mon Oct 18 11:05:27 2006
 Plot Scale: 1/8" = 50'-0" / 1" = 100'-0"
 User Name: rnk1baule

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY _____		CHECKED BY _____