

GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 301 (US 20)	(2,3,4)RS	Winnebago	16	6
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64A21				

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

AT&T Communications	West Shore Pipeline Co.
Commonwealth Edison Co.	Verizon
SBC/Ameritech Telephone Co.	NICOR Gas Co.
Rock River Water Reclamation Dist.	Insight Communications of Rockford
Norlight Telecommunications	Aldridge Electric

Following are the known utilities located within the project limits or immediately adjacent to the project construction limits which are not members of JULIE and should be notified individually by the contractor:

Mr. John Martin
 Rockford Water Department
 425 E. State Street
 Rockford, IL 61104
 Ph. 815/961-3764

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

The Contractor shall layout stations for the project using the stationing on the plans. Also, separate stationing shall be required for the stamping of stationing in the pavement based on new stationing. The horizontal control for new stationing for the pavement stamping shall be laid out according to horizontal and vertical control sheets. The layout of the stationing can be done with a wheel or tape and shall be adjusted according to the stations at existing culverts or side roads and streets. The cost of layout stationing shall be included in the cost of Construction Layout.

All ramps scheduled for resurfacing are for the gore areas except the northwest and southwest ramps at Alpine Road, which length is for the ramp to the existing concrete pavement.

Program #5
 (Arch. Size)
 Enlarge
 200%
 Enlarge 107%