CONTRACT NO. 64A21

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	(2,3,4)BS	WINNEBAGO	96	14
STA. _____	TO STA. _____			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

LOCATION	COMMENT	FOOT
US 20 EB		
307 + 25 - 310 + 77		352
329 + 49 - 332 + 14		265
445 + 36 - 448 + 6		270
468 + 44 - 470 + 11		167
544 + 23 - 548 + 9		386
568 + 16 - 568 + 61		45
663 + 61 - 666 + 83		322
685 + 34 - 686 + 99		165
702 + 30 - 707 + 65		535
EB Ramps		
307 + 5 - 310 + 87		382
329 + 2 - 332 + 14		312
332 + 14 - 334 + 56	Skip Dash	60
445 + 36 - 448 + 6		270
468 + 44 - 478 + 11		967
544 + 23 - 548 + 11		388
568 + 16 - 569 + 78		162
569 + 78 - 572 + 41		263
663 + 61 - 667 + 28	Skip Dash	70
684 + 89 - 686 + 99		210
686 + 0 - 692 + 15	Skip Dash	120
702 + 30 - 707 + 58		528
US 20 WB		
308 + 31 - 310 + 44		213
329 + 12 - 332 + 50		338
446 + 41 - 448 + 67		226
467 + 7 - 471 + 92		485
568 + 1 - 572 + 15		414
685 + 14 - 688 + 20		306
WB Ramps		
308 + 31 - 310 + 89		258
328 + 67 - 332 + 50		383
444 + 61 - 446 + 41	Skip Dash	50
471 + 92 - 497 + 93		2601
543 + 81 - 546 + 25	Skip Dash	
546 + 25 - 548 + 3		178
568 + 1 - 572 + 15		414
664 + 40 - 666 + 69	Skip Dash	60
666 + 69 - 668 + 33		164
684 + 69 - 688 + 20		351
	TOTAL	12680

78000620 THERMOPLASTIC PAVEMENT MARKING - LINE 18"

LOCATION	COMMENT	FOOT
US 20 EB		
282 + 68	Aerial speed check zone	12
289 + 28	Aerial speed check zone	12
295 + 88	Aerial speed check zone	12
US 20 WB		
356 + 83	Aerial speed check zone	12
363 + 43	Aerial speed check zone	12
370 + 3	Aerial speed check zone	12
	TOTAL	72

78003130 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"

LOCATION	COMMENT	LENGT FOOT	6" LINE FOOT
US 20 EB			
275 + 75 - 448 + 6	Skip dash (White)	17231	4310
468 + 44 - 548 + 9	Skip dash (White)	7965	1990
568 + 16 - 707 + 65	Skip dash (White)	13949	3490
686 + 99 - 692 + 15	Skip dash (White)	516	130
US 20 WB			
276 + 74 - 448 + 67	Skip dash (White)	17193	4300
467 + 7 - 547 + 90	Skip dash (White)	8083	2020
568 + 1 - 707 + 65	Skip dash (White)	13964	3490
	TOTAL		19730

78008310 POLYUREA PAVEMENT MARKING TYPE 2 - LINE 4"

LOCATION	COMMENT	4" LINE FOOT
US 20 EB		
275 + 30 - 448 + 2	Edge line (Yellow)	17272
275 + 30 - 304 + 5	Edge line (White)	2875
310 + 77 - 329 + 49	Edge line (White)	1872
341 + 60 - 440 + 34	Edge line (White)	9874
468 + 44 - 548 + 7	Edge line (Yellow)	7963
483 + 34 - 540 + 44	Edge line (White)	5710
568 + 16 - 707 + 65	Edge line (Yellow)	13949
575 + 39 - 659 + 76	Edge line (White)	8437
666 + 83 - 685 + 34	Edge line (White)	1851
692 + 15 - 707 + 11	Edge line (White)	1496
EB Ramps		
304 + 5 - 310 + 77	Edge line (White)	672
329 + 49 - 341 + 60	Edge line (White)	1211
440 + 34 - 448 + 6	Edge line (White)	772
468 + 44 - 483 + 34	Edge line (White)	1490
540 + 44 - 548 + 11	Edge line (White)	767
568 + 16 - 575 + 39	Edge line (White)	723
659 + 76 - 666 + 83	Edge line (White)	707
685 + 34 - 692 + 15	Edge line (White)	681
701 + 24 - 707 + 58	Edge line (White)	634
US 20 WB		
275 + 30 - 449 + 27	Edge line (Yellow)	17397
276 + 74 - 298 + 52	Edge line (White)	2178
310 + 44 - 329 + 12	Edge line (White)	1868
336 + 49 - 438 + 45	Edge line (White)	10196
467 + 91 - 547 + 99	Edge line (Yellow)	8008
475 + 65 - 535 + 84	Edge line (White)	6019
567 + 93 - 707 + 65	Edge line (Yellow)	13972
575 + 73 - 655 + 58	Edge line (White)	7985
667 + 88 - 685 + 14	Edge line (White)	1726
692 + 8 - 707 + 11	Edge line (White)	1503
WB Ramps		
298 + 52 - 310 + 89	Edge line (White)	1237
328 + 67 - 336 + 49	Edge line (White)	782
438 + 45 - 448 + 67	Edge line (White)	1022
475 + 65 - 497 + 93	Edge line (White)	2228
535 + 84 - 548 + 3	Edge line (White)	1219
568 + 1 - 575 + 73	Edge line (White)	772
655 + 58 - 668 + 33	Edge line (White)	1275
684 + 69 - 692 + 8	Edge line (White)	739
	TOTAL	159082

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Wed Oct 25 13:59:02 2006
FILE NAME = P:\Excel\US20cunninghamtel39\bpms28\gpscalb.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = mcklaus