

F.A.P. R'E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	12.3.416S	WINNEBAGO	46	21
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

PATCHING SCHEDULE

STATION	WIDTH OF LANE FT	LENGTH OF PATCH		44200970		44200974		44200976		44002214		40601005		44213200	Z0017100	Z0075300	44213100	
		CLASS B PATCH TYPE II, 10 INCH		CLASS B PATCH TYPE III, 10 INCH		CLASS B PATCH TYPE IV, 10 INCH		HMA RM OV PATCH 3 1/2		HMA REPL OVER PATCH		SAWING	DOWEL BARS	TIE BARS	PAVEMENT FABRIC			
		LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	(3W+FL)	(each)	(each)	SQ YD	
		FT	FT	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	TONS	TONS	(feet)	(each)	(each)	SQ YD	
EB																		
279 + 29	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
279 + 96	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
288 + 26	12		8		10.7						12.00		2.35	52	20			
297 + 4	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
303 + 15	12	30	30					40.0	40.0	41.33	41.33	8.10	8.10	162	40	14	80.0	
317 + 11	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
318 + 11	12	12	12			16.0	16.0			17.33	17.33	3.40	3.40	108	40		32.0	
336 + 19	12	10	10	13.3	13.3					14.67	14.67	2.87	2.87	102	40			
341 + 70	12	15	12			20.0	16.0			21.33	17.33	4.18	3.40	114	40		36.0	
343 + 43	12	6		8.0						9.33		1.83		48	20			
353 + 75	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
359 + 80	12	31	31					41.3	41.3	42.67	42.67	8.36	8.36	165	40	15	82.7	
376 + 21	12	10	10	13.3	13.3					14.67	14.67	2.87	2.87	102	40			
378 + 85	12	8		10.7						12.00		2.35		52	20			
395 + 11	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
396 + 55	12		6		8.0						9.33		1.83	48	20			
403 + 44	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
404 + 14	12	6	6	8.0	8.0					9.33	9.33	1.83	1.83	90	40			
406 + 56	12	6	6	8.0	8.0					9.33	9.33	1.83	1.83	90	40			
408 + 11	12	6	6	8.0	8.0					9.33	9.33	1.83	1.83	90	40			
410 + 97	12	6	6	8.0	8.0					9.33	9.33	1.83	1.83	90	40			
414 + 39	12	6	6	8.0	8.0					9.33	9.33	1.83	1.83	90	40			
417 + 33	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
427 + 40	12		33					44.0			45.33		8.89	102	20	16	44.0	
433 + 81	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
483 + 43	12	8	8	10.7	10.7					12.00	12.00	2.35	2.35	96	40			
484 + 43	12	6	6	8.0	8.0					9.33	9.33	1.83	1.83	90	40			
488 + 53	12	6	6	8.0	8.0					9.33	9.33	1.83	1.83	90	40			
489 + 20	12	20	20					26.7	26.7	28.00	28.00	5.49	5.49	132	40	9	53.3	
492 + 21	12	15	15			20.0	20.0			21.33	21.33	4.18	4.18	117	40		40.0	
PAGE SUB-TOTAL				208.0	208.0	56.0	52.0	108.0	152.0	408.0	449.3	80.0	88.1	2894.0	1100.0	54.0	368.0	
FULL DEPTH PAGE SUBTOTAL (40% of sub-total)				83.2	83.2	22.4	20.8	43.2	60.8									

PLOT DATE = Nov 15 10:45:59 2006
 FILE NAME = P:\S\11\US26\...
 PLOT SCALE = 5/8"=1'-0"
 USER NAME = mch1male

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE

DRAWN BY
CHECKED BY