CONTRACT NO. 64C54 F.A.P. SECTION COUNTY TOTAL SHEET NO. 734 (77-1)TS-3 WINNEBAGO 10

FEO. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

	UTILITIES		
NAME	TYPE	TELEPHONE	JULIE MEMBER
MR. DAVE SCHACHT	ELECTRIC	630-437-2129	
COMMONWEALTH EDISON CO.			800-892-0123
123 ENERGY AVE			
ROCKFORD, IL 61109			
MR. KALIN HINSHAW	TELEPHONE	815-895-1515	YES
VERIZON		-	800-892-0123
112 WEST ELM STREET			
SYCAMORE IL 60178			
MR. JEREMY SCHNACK	TELEPHONE	309-793-4456	
AT&T			800-892-0123
635 - 18TH STREET			
ROCK ISLAND, IL 61201			
MR. GARY QUADE	ELECTRIC	563-584-7395	YES
ALLIANT ENERGY			800-892-0123
P.O. BOX 77007			
MADISON WI 53707-1007			
	GAS	630-983-8676	
NICOR GAS CO.			800-892-0123
1844 FERRY ROAD			
NAPERVILLE IL 60563-9600			
ME MARK BURKS	TELEPHONE	217-854-4013	YES
CITIZENS			800-892-0123
225 NORTH BROAD	1		
CARLINVILLE IL 62626			
MR. PAUL BAUMANN	TELEPHONE	217-525-0078	
McLEOD USA			800-892-0123
900 COMMERCE DRIVE SUITE 203			
OAK BROOK IL 60523			
MR. EDWARD RICE	WATER & SEWER	815-624-7600	NO
VILLAGE OF ROCKTON			
110 E MAIN STREET			
ROCKTON IL 61072			
MR. BRIAN HEDRINGTON	WATER & SEWER	815-389-3023	NO
CITY OF SOUTH BELOIT			
519 BLACKHAWK BLVD			
SOUTH BELOIT IL 61080		000 705 775	
MR. KEITH STEWART	COMMUNICATIONS	608-365-3382	
CHARTER COMMUNICATIONS			800-892-0123
1837 PARK AVENUE			
BELOIT WI 53511			

<u> </u>						
REVISIONS		ILLINOIS	DEPARTMENT	OF	TRANSPORTATION	
NAME DATE	DAIL					
		SCALE: VERT.			DRAWN BY	
		DATE HORIZ.			CHECKED BY	
 l						

GENERAL NOTES:
1. THE MOUNTING HEIGHT OF THE LUMINAIRES ON THE PROPOSED COMBINATION MAST- ARM ASSEMBLIES AT THE INTERSECTION OF IL 2 WITH PRAIRIE HILL SHALL BE 40' HORIZONTAL MOUNTED

2. THE PAY ITEM "REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT" SHALL BE PREFORMED BY THE CONTRACTOR AND SHALL INCLUDE ALL MATERIAL AND LABOR TO COMPLETE.
THE FOLLOWING SHALL BE REMOVED AND BY THE CONTRACTOR AND RETAINED BY THE CONTRACTOR FOR SALVAGE VALUE.

12 EACH - 1-FACE, 3-SECTION SIGNAL HEAD 4 EACH - 1-FACE, PEDESTRAIN SIGNAL HEAD 2 EACH - PEDESTRAIN PUSH BUTTON 2 EACH - SERVICE DISCONNECT 2- EACH CONTROLLER AND CABINET 1- EACH CABINET FOUNDATION 3 EACH - SIGNAL POST AND FOUNDATION ALL LIN FT ELECTRIC CABLE BEING REPLACED

ALL MATERIAL UNMENTIONED ABOVE SHALL BE REMOVED BY THE CONTRACTOR AND RETAINED BY THE CONTRACTOR FOR SALVAGE. ANY HOLES RESULTING FROM REMOVAL OR RELOCATION OF SIGNAL

3. NO SIGNAL WORK SHALL BE ALLOWED UNTIL ALL COMPONENT FOR THE MODIFICATION OF THE SIGNAL AT THE LOCATIONS LISTED IN THIS CONTRACT HAVE ARRIVED AT THE JOB SITE.

4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTILCE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123.

THE FOLLOWING LISTED ARE KNOWN UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THIS PROJECT.

GENERAL NOTES - UTILITIES