

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION


| ROUTE NO. | SECTION | co | INTY | TOTAL SHEUTS | SHEET ND. | SHE | ET : | NO. | |
|---------------|-----------|----------------------|------|-----------------|--------------|-----|------|-----|--|
| F.A.P. 693 | (119B-3)I | TAZEWELL | | 31 | 12 | 14 | SHE | ETS | |
| ED. ROAD DIS | T. NO. 7 | DLLINGIS FEO. AID PR | | OJECT- | | | | | |

Contract #68415



PLAN






CLAMPING PLATE

SHEAR KEY CLAMPING DETAILS AT STAGE CONST. JT.

Cost included with Precast Prestressed Concrete
Deck Beams (27" Depth),
See Stage Construction Details for traffic lanes.
See Article 504.06 (d) of the Standard Specifications
For Stage Construction of Precast Prestressed
Concrete Deck Beams.

TEMPORARY CONCRETE BARRIER AND
STAGE CONSTRUCTION DETAILS
ILLINOIS ROUTE 9 OVER
PRAIRIE CREEK
F.A.P. ROUTE 693 SECTION (119B-3)I
TAZEWELL COUNTY
SN 090-0061



NOTES

The 1" ϕ high strength bolts used to connect the wood blocks shall be tightened to a snug fit without crushing the wood block. The wing type threaded insert assembly shall be spaced 6'-0" longitudinally.

The Waterproofing Membrane shall extend under the Temporary Concrete Barrier without the asphalt sand seal protection layer. Once the Temporary Concrete Barrier has been removed, and the penetrating primer, coal tar emulsion, coal tar emulsion and fiberglass fabric, and coal tar emulsion slurry layers of the Waterproofing Membrane is lapped 6", the asphalt sand seal protection layer shall be applied according to Article 581 of the Standard Specifications.


The cost for H.S. bolts, flat headed washers, and wood block is included with Temporary Concrete Barrier.

The cost for wing type threaded inserts is included with Precast Prestressed Concrete Deck Beams (27" Depth).


EXISTING PPC DECK BEAMS

NEW PPC DECK BEAMS

SECTIONS THRU PPC DECK BEAMS



| INSERT | DE | TAIL | |
|--------|----|------|---|
| | | | • |



DETAIL I

The Temporary Concrete Barrier and wood blocks shall not be removed until Stage II Construction PPC Deck Beams have been placed and shear keys grouted.

| DESIGNED | BWP | THOUVENOT, WADE & |
|----------|-----|--------------------------------------------------------------------------|
| | | MOERCHEN, INC. |
| CHECKED | ALN | (TWII) |
| DRAWN | BWP | CORPORATE OFFICE 4940 OLD COLLINSVILLE RD. SWANSEA, ILLINOIS 62226 |
| CHECKED | KPC | TEL (618) 624-4488 FAX (618) 624-6688 E-MAIL: oorpatwm-inc.com |