

# SUMMARY OF QUANTITIES

F.A.B. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
645	(105BR) 1-1	MARSHALL	9	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

100% STATE SAFETY-2A  
MARSHALL COUNTY

CODE NO.	ITEM	UNIT	TOTAL
40603335	Hot - Mi x Asphal t Surface Course, Mi x " D ", N50	TON	25.2
<b>44001005</b>	Hot - Mi x Asphal t Surface Removal	SQ YD	45
50400305	Precast Prestressed Concrete Deck Beams (17" Depth)	SQ FT	1091
50900905	Removi ng and Re- erecti ng Exi sti ng Rai li ng	FOOT	79
58100200	Waterproofi ng Membrane System	SQ YD	168
58300100	<b>PORTLAND CEMENT MORTAR FAIRING COURSE</b>	FOOT	406
67000400	Engi neer' s Fi el d Offi ce, Type A	CAL MO	5
67100100	Mobi li zati on	L SUM	1
70100405	Traffi c Control and Protecti on Standard 701321	<b>EACH</b>	1
70100450	Traffi c Control and Protecti on, Standard 701201	L SUM	1
70300220	Temporary Pavement Marki ng - Line 4"	FOOT	<b>196</b>
70301000	Work Zone Pavement Marki ng Removal	SQ FT	<b>536</b>
70400100	Temporary Concrete Barri er	FOOT	<b>348</b>
* 78001110	Paint Pavement Marki ng - Line 4"	FOOT	<b>1,396</b>
78300100	Pavement Marki ng Removal	SQ FT	<b>67</b>
89502500	Remove Temporary Traffic Signal Instal lati on	EACH	1
X0301424	Si li cone Joi nt Seal er	FOOT	40
X0320047	Removal of Exi sti ng Precast Prestressed Concrete Deck Beams	SQ FT	1095
X0320887	Pol ymer Concrete	CU FT	5
* X7200200	Wi de Load Si gni ng	L SUM	1
Z0001900	Asbestos Bearing Pad Removal	EACH	9
⊙ Z0030250	Impact Attenuators Temporary (Non-Redi recti ve) Test Level 3	EACH	2

⊙ SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
DRAWN BY BTS  
CHECKED BY  
DATE 10-11-2006

PLOT DATE \* DATE  
PLOT SCALE \* SCALE  
PLOT SPACE \* REF