

P.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	110-4.5MRS	VERMILION	13	4

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI 74
OAKWOOD INTERCHANGE
EB EXIT RAMP "A"
STATION 107+39.08
TO
STATION 109+04.08
VERMILION COUNTY
100% STATE
1000 - 2A

FAI 74
OAKWOOD INTERCHANGE
WB EXIT RAMP "D"
STATION 105+05.31
TO
STATION 109+05.31
VERMILION COUNTY
100% STATE
1000 - 2A

CONSTRUCTION TYPE CODE:

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	151.0	55.0	96.0
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	85.0	31.0	54.0
40600990	TEMPORARY RAMP	SQ YD	182.0	93.0	89.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	128.0	47.0	81.0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	1,509.0	549.0	960.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.5	0.5
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	864.0	194.0	670.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	365.0	190.0	175.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	291.0	156.0	135.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	72.0	36.0	36.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	39.0	17.0	22.0

* SPECIALTY ITEM