# INDEX OF SHEETS

- COVER SHEET
- INDEX OF SHEETS, HIGHWAY STANDARDS,
- **GENERAL NOTES & COMMITMENTS**
- **SUMMARY OF QUANTITES**
- TYPICAL SECTIONS
- SCHEDULES
- TIE POINTS & BENCHMARKS
- REMOVAL PLAN
- **PLAN & PROFILES** 8-9
- 10-12 OMITTED
- **PAVEMENT MARKING** 13
- 14-15 MISCELLANEOUS DETAILS
- BRIDGE PLANS (SHEET 18 OMITTED) 16-27
- CHANNEL CROSS SECTIONS 28-29

### **HIGHWAY STANDARDS**

00000104	631032-03	701311-02
420401-05	63500602	70200106
51500102	63501101	780001-01
63000107	70101101	781001-02
631011-03	701301-02	BLR 21-6

#### GENERAL NOTES:

- 1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- 3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
  - SCOTT AIR FORCE BASE (COMMUNICATIONS) SBC (COMMUNICATIONS)
  - \* VERIZON NORTH, INC (COMMUNICATIONS)
  - . BI-STATE DEVELOPMENT AGENCY (ELECTRIC)
  - \* ILLINOIS AMERICAN WATER CO.
  - \* AMEREN IP (GAS & ELECTRIC)
  - . CITY OF BELLEVILLE (SANITARY SEWER)

MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY \*. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

- 4. ANY REFERENCE TO "BITUMINOUS CONCRETE" SHALL BE CONSTRUED TO DENOTE "HOT-MIX ASPHALT".
- 5. THE WIDTHS OF BITUMINOUS SURFACE REMOVAL SHOWN ON THE PLANS ARE THE NOMINAL WIDTHS. IRREGULARITIES IN THE SURFACE WIDTH MAY OCCUR THROUGHOUT THE LENGTH OF THE SECTION. BITUMINOUS SURFACE REMOVAL WILL BE PAID FOR IN SQUARE METERS BASED UPON THE NOMINAL WIDTHS INDICATED.
- 6. ALL SIGNS THAT INTERFERE WITH CONSTRUCTION OPERATIONS SHALL BE REMOVED, STORED AND RE-ERECTED ACCORDING TO ARTICLE 107.25 OF THE STANDARD SPECIFICATIONS. ANY DAMAGE TO SIGNS CAUSED BY CONSTRUCTION ACTIVITIES SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- 7. EXISTING RIPRAP AND CONCRETE "WASH-OUT" LOCATED IN THE CHANNEL SHALL BE REMOVED DURING CHANNEL EXCAVATION. THE COST FOR THIS REMOVAL SHALL BE INCLUDED IN THE COST OF "CHANNEL EXCAVATION" AND NO OTHER COMPENSATION WILL BE PERMITTED.
- 8. EXISTING PLANS ARE NOT INCLUDED DUE TO THEIR POOR CLARITY. A COPY WILL REMAIN IN THE DESIGN FILE FOR REFERENCE.

## EROSION CONTROL PLAN

ANY AREAS DISTRUBED DUE TO CONSTRUCTION ACTIVITES SHALL BE SEEDED (TEMPORARY AND PERMANENT) AT THE CONTRACTOR'S EXPENSE AND NO OTHER COMPENSATION WILL BE PERMITTED.

ALL EROSION CONTROL PRODUCTS FURNISHED SHALL BE SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR THE USE SPECIFIED IN THE EROSION CONTROL PLAN. PRIOR TO THE APPROVAL AND USE OF THE PRODUCT, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A NOTARIZED CERTIFICATION BY THE PRODUCER STATING THE INTENDED USE OF THE PRODUCT AND THAT THE PHYSICAL PROPERTIES REQUIRED FOR THIS APPLICATION ARE MET OR EXCEEDED. THE CONTRACTOR SHALL PROVIDE MANUFACTURER RECOMMENDED INSTALLATION PROCEDURES TO FACILITATE THE ENGINEER IN CONSTRUCTION INSPECTION.

TEMPORARY SEEDING SHALL BE COMPLETED ON A WEEKLY BASIS ON EXPOSED GROUND AND SHALL BE IN ACCORDANCE WITH SECTION 280 OF THE STANDARD SPECIFICATIONS. TEMPORARY EROSION CONTROL SEEDING SHALL BE APPLIED AT A RATE OF 100 LBS/ACRE.

EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.

FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.

### COMMITMENTS

A COMMITMENT HAS BEEN MADE TO SCOTT AIR FORCE BASE THAT ALL WORK REQUIRING LANE RESTRICTIONS WILL BE COMPLETE AND THE STRUCTURE RE-OPENED WITHOUT RESTRICTION BY JUNE 15, 2007. FURTHERMORE, THE CONTRACTOR WILL ONLY BE PERMITTED TO CONSECUTIVE CALENDAR DAYS OF CLOSURE IN ORDER TO COMPLETE THE WORK.

THE SCOTT AIR FORCE BASE BELLEVILLE GATE WILL BE RE-OPENED PRIOR TO THE SCOTT AIR FORCE BASE ATR SHOW WHICH WILL BE HELD ON JULY 6-7, 2007.

THE VETERANS OF FOREIGN WARS POST 4183 HAS AGREED TO TEMPORARY CLOSURE OF THIER NORTH ENTRANCE. LOCATED AT STA 98+98.05 (RT), IF NECESSARY. THE SOUTH ENTRANCE LOCATED AT STA 98+13.54 (RT) MUST REMAIN OPEN AT ALL TIMES.

SCOTT AIR FORCE BASE AND THE VFW HALL SHALL BE INFORMED 2 WEEKS PRIOR TO CLOSURE.

SCOTT AIR FORCE BASE CONTACT: MR. DOUG BRIGGS 618-256-2639

VETERANS OF FOREIGN WARS POST 4183 CONTACT: MR. J.C. GRANTHAM 618-746-9801

MAJOR RANDY C.A. WHITECOTTON 618-256-4823

ILLINOIS DEPARTMENT OF TRANSPORTATION INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS

> FAU ROUTE 9177 SECTION 44-1BR ST. CLAIR COUNTY

CONTRACT NO. 76566

COUNTY TOTAL SHEET NO.

ST. CLAIR 29 2

TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

SECTION

44-18R

9177

STA.